

### ஒப்பந்தப்புள்ளி அறிவிப்பு

புவனகிரி பேரூராட்சி எல்கையில் பிற்படுத்தப்பட்ட பகுதிக்கான மான்ய நிதி திட்டம் 2007-08 -ன்கீழ் அட்டவணையில் குறிப்பிட்ட திட்ட பணியினை மேற்கொள்ள ஒப்பந்ததாரர்களிடமிருந்து மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகள் 06.07.2009 திங்கட்கிழமை மாலை 3.00 மணி வரை பேரூராட்சி அலுவலகத்தில் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் கீழ்க்காணும் நிபந்தனைக்குட்பட்டு பெற்றுக்கொள்ளப்படும். வரபெற்ற ஒப்பந்தப்புள்ளிகள் அன்றைய தினம் 06.07.2009 மாலை 3.30 மணியளவில் ஆஜராகி உள்ள ஒப்பந்ததாரர்கள் முன்னிலையில் திறக்கப்படும். வேலைக்குண்டான ஒப்பந்த புள்ளி நமூனா உரிய கட்டணம் செலுத்தி 03.07.2009 வெள்ளிக்கிழமை மாலை 4.00 மணி வரை பேரூராட்சி அலுவலகத்தில் பெற்றுக்கொள்ளலாம்.

வ. எண்	பணியின் விவரம்	மதிப்பீடு (லட்சத்தில்)	டேவணித் தொகை	ஒப்பந்தப் புள்ளி நமூனா கட்டணம்	பணியினை முடிக்க வேண்டிய காலம்
<b>பிற்படுத்தப்பட்ட பகுதிக்கான மான்ய நிதி திட்டம் 2007-08</b>					
1.	ஆதிவராகநத்தம் காலனி தெரு தார்சாலை அமைத்தல்	3.00	3000/-	780/-	60- நாட்கள்
2.	புதுக்குப்பம் மெயின்ரோடு தார்சாலை அமைத்தல்	2.10	2100/-	780/-	45-நாட்கள்
3.	ஈஸ்வரன் கோயில் தெரு தார்சாலை அமைத்தல் (அகலபடுத்தி 200மீ உறுதிபடுத்துதல்)	2.60	2600/-	780/-	60- நாட்கள்
4.	ஆதிவராகநத்தம் மேல்நிலை நீர் தேக்கதொட்டிதெரு தார்சாலை அமைத்தல்	1.75	1750/-	780/-	60- நாட்கள்
5.	சுவீகாரடத்தெரு தார்சாலை அமைத்தல்	2.05	2050/-	780/-	45- நாட்கள்
6.	புதுப்பிள்ளையார் கோயில் சந்து சிமெண்ட் சாலை அமைத்தல்	3.00	3000/-	780/-	60- நாட்கள்
7.	லட்சுமி நகர் தார்சாலை அமைத்தல்	2.15	2150/-	780/-	60- நாட்கள்
8.	கொத்ததெரு சிமெண்ட் சாலை அமைத்தல்	1.89	1890/-	780/-	45- நாட்கள்
<b>மொத்தம்</b>		<b>18.54</b>			

#### நிபந்தனைகள்

- ஒப்பந்தப்புள்ளிகள் குறிப்பிட்ட காலக்கெடுவுக்குள் உரிய ஒப்பந்த புள்ளி படிவத்தில் பூர்த்தி செய்து கொடுக்கப்பட வேண்டும். காப்புத்தொகை செலுத்தாத ஒப்பந்தப்புள்ளிகளும் காலங்கடந்து வரும் ஒப்பந்தப்புள்ளிகளும் பரிசீலனைக்கு எடுத்துக் கொள்ளப்பட மாட்டாது.
- ஒப்பந்ததாரர் வேலை செய்ய ஆணை வழங்கப்பட்ட உடன் பணி ஆரம்பிக்கும் முன்னர் ரூபாய் 20/- மதிப்புள்ள முத்திரைத்தாளில் ஒப்பந்த உடன் படிக்கை எழுதிக்கொடுக்க வேண்டும்.
- பணியினை ஆரம்பிக்கும் முன்னர் பொறியியல் அலுவலர்களின் ஆலோசனை பெற்று அதன்படி பணியினை செய்ய வேண்டும்.
- பட்டியல் வரப்பட்டவுடன் ஒப்பந்தக்காரர்களுக்கு விதிகளின்படி தொகை பட்டுவாடா செய்யப்படும்.
- மதிப்பீட்டு தொகைக்கு சொத்து மதிப்பு உள்ளவர்கள் மட்டுமே டேவணித்தொகையை செலுத்தி ஒப்பந்தப்புள்ளிகள் கொடுக்க வேண்டும்.
- செயல் அலுவலரால் அவ்வப்போது பிறப்பிக்கப்படும் இதர நிபந்தனைகள்.

செயல் அலுவலர்  
புவனகிரி பேரூராட்சி.

**பெறுதல் :** அனைத்து பதிவுப்பெற்ற ஒப்பந்ததாரர்கள் , பேரூராட்சி, புவனகிரி.

**நகல் :** அலுவலக விளம்பரப்பலகை

**நகல் :** தலைவர், உபத்தலைவர், உறுப்பினர்கள், புவனகிரி பேரூராட்சி.

**நகல் :** திட்ட அலுவலர், மாவட்ட ஊரக வளர்ச்சி முகமை, கடலூர் அவர்களுக்கு தகவலுக்காக பணிநிதனுப்பப்படுகிறது.

**நகல் :** உதவி இயக்குநர், பேரூராட்சிகள் கடலூர் மண்டலம், கடலூர் அவர்களுக்கு தகவலுக்காக பணிநிதனுப்பப்படுகிறது.

**நகல் :** உதவி செயற்பொறியாளர், பேரூராட்சி பணிகள், உதவி இயக்குநர் அலுவலகம், கடலூர் அவர்களுக்கு தகவலுக்காக பணிநிதனுப்பப்படுகிறது.

**நகல் :** இளநிலை பொறியாளர், பேரூராட்சி பணிகள், அண்ணாமலைநகர் தகவலுக்காக.

**நகல் :** செயல் அலுவலர், பரங்கிப்பேட்டை, அண்ணாமலைநகர், வடலூர், சேத்தியாதோப்பு, காட்டுமன்னார்குடி, கிள்ளை, லால்பேட்டை பேரூராட்சிகள் தகவலுக்காக.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING PREMIX CARPET WITH SEAL COAT AT ADHIVARAGANATHAM AD COLONY IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
 EMD : 3,00,000/- Executive Officer  
 DATE OF TENDER : 06.07.2009 Town Panchayat  
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	31.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	1144.00 Sqm	Picking the existing worn out WBM surface including sectioning and replace the metal to camber with power roller rolling etc completed as per standard specification.		One Squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	86.50 Cum	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade-III using 1.00 cum. Of 53 mm to 22.4 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I. Value of less than 6 for blindage for 10 sqm. of 75 mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental guage for premeasurement, labour charges blinding with grave, watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction, hire, fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights etc., complete as per standard specification, for Top layer (payment shall be made for finished item of work after compaction.)		One cubic metre		
4.	1144.00 Sqm	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
5.	1144.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One squire metre		
6.	28.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge Packing).		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING PREMIX CARPET WITH SEAL COAT AT PUDUKKUPPAM MAIN ROAD  
IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
EMD : 2,10,000/- Executive Officer  
DATE OF TENDER : 06.07.2009 Town Panchayat  
CHALLAN NO : Bhuvanagiri.

- B) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/ MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	49.00 Cum	Earth work excavation in all classes of soils such as hard stiffy clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	810.00 Sqm	Picking the existing worn out WBM surface including sectioning and replace the metal to camber with power roller rolling etc completed as per standard specification.		One Squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	61.00 Cum	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade-III using 1.00 cum. Of 53 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I. Value of less than 6 for blindage for 10 sqm. of 75 mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental guage for premeasurement, labour charges blinding with grave, watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction, hire, fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights etc., complete as per standard specification, for Top layer (payment shall be made for finished item of work after compaction.)		One cubic metre		
4.	810.00 Sqm	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
5.	810.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One squire metre		
6.	25.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge Packing).		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** WIDENING AND STRENGTHENING AT ESWARAN KOIL STREET IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
 EMD : 2,60,000/- Executive Officer  
 DATE OF TENDER : 06.07.2009 Town Panchayat  
 CHALLAN NO : Bhuvanagiri.

- C) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/ MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	12.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	72.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed. as per standard specification.		One cubic metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	45.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –II using 1.00 cum of 63 mm to 45mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification.		One cubic metre		
4.	150.00 Sqm	Picking the existing worn out WBM surface including sectioning and replace the metal to camber with power roller rolling etc completed as per standard specification.		One squire metre		
5.	57.00 Cum	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade-III using 1.00 cum. Of 53 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I. Value of less than 6 for blindage for 10 sqm. of 75 mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental guage for premeasurement, labour charges blinding with grave, watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction, hire, fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights etc., complete as per standard specification, for Top layer (payment shall be made for finished item of work after compaction.)		One cubic metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
6.	750.00 Sqm	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete		One squire metre		
7.	750.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One squire metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING PREMIX CARPET WITH SEAL COAT AT ADHIVARAGANATHAM OHT STREET  
IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
EMD : 1,75,000/- Executive Officer  
DATE OF TENDER : 06.07.2009 Town Panchayat  
CHALLAN NO : Bhuvanagiri.

- D) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/ MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	11.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	75.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed as per standard specification.		One cubic metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	34.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –II using 1.00 cum of (63 mm to 45mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete.		One cubic metre		
4.	34.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification.		One cubic metre		
5.	450.00 Sqm	Providing tack coat over WBM surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
6.	450.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One squire metre		
7.	21.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge Packing).		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING PREMIX CARPET WITH SEAL COAT AT SUVIKARA EDA STREET  
IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
EMD : 2,05,000/- Executive Officer  
DATE OF TENDER : 06.07.2009 Town Panchayat  
CHALLAN NO : Bhuvanagiri.

- E) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/ MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	17.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	753.00 Cum	Picking the existing worn out BT surface 3 to 5 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to camber sectioning, leveling, etc., complete as including labour charges for picking and other tools and plants etc complete as per standard specification.		One cubic metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	11.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –II using 1.00 cum of (63 mm to 45mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete.		One cubic metre		
4.	57.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification.		One cubic metre		
5.	753.00 Sqm	Providing tack coat over WBM surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
6.	753.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One squire metre		
7.	12.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge Packing).		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING CEMENT CONCRETE PAVEMENT @ PUDU PILLAIYAR KOIL LANE IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
 EMD : 3,00,000/- Executive Officer  
 DATE OF TENDER : 06.07.2009 Town Panchayat  
 CHALLAN NO : Bhuvanagiri.

- F) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	27.00 Cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stony each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus earch as shown by the departmental officers at site as per standard specifications.		One cubic metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
2.	219.00 Sqm	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including conveyance of all materials to work site and other incidental charges etc., complete.		One squire metre		
3.	44.00 Cum	Cement concrete 1:5:10 (One cement five sand and ten hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.		One cubic metre		
4.	66.00 Cum	Cement concrete 1:2:4 (One cement Two sand and Four hard broken) Using 20mm ISS gauge hard broken granite stone jelly for foundation including watering wherever necessary and in layers not more than 15 cm in thick etc., including compacting and fixing the expansion joint of bitumen pad and all materials to site and all labour charges and all other including charges etc., completed.		One cubic metre		
5.	15.00 Sqm	Providing and fixing Bitumen expansion pad including cost and convince of Bitumen Pad and fixing in proper position etc., completed as per standard specification as directed by Engineer. Incharge.		One squire metre		
6.	27.00 Cum	Spreading U.S. gravel to specified thick including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge packing)		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING PREMIX CARPET WITH SEAL COAT AT LAKSHMI NAGAR  
IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
EMD : 2,15,000/- Executive Officer  
DATE OF TENDER : 06.07.2009 Town Panchayat  
CHALLAN NO : Bhuvanagiri.

- G) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/ MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	351.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	104.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed as per standard specification.		One cubic metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	37.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –II using 1.00 cum of (63 mm to 45mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete.		One cubic metre		
4.	37.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification.		One cubic metre		
5.	488.00 Sqm	Providing tack coat over WBM surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
6.	488.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One squire metre		
7.	18.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge Packing).		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.

**BHUVANAGIRI TOWN PANCHAYAT****TENDER SCHEDULE**

**NAME OF WORK :** PROVIDING CEMENT CONCRETE PAVEMENT @ KOTHA STREET  
IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :  
EMD : 1,89,000/- Executive Officer  
DATE OF TENDER : 06.07.2009 Town Panchayat  
CHALLAN NO : Bhuvanagiri.

- H) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net ( Not with standing any custom or practice to the contrary ) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No.	Probable Quantity	Description of Work	SSRB/ MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
1.	29.00 Cum	Earth work excavation in all classes of soils such as hard stiffy clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	407.00 Sqm	Picking the existing the worn out BT surface 3 to 5 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to camber sectioning, leveling, etc., complete as per including labour charges for picking and other tools and plants etc., complete as per standard specification.		One squire metre		

Item No.	Probable Quantity	Description of Work	SSRB/MOST	Unit in Words	Rate In	
					Figures	Words
1	2	3	4	5	6	7
3.	176.00 Sqm	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including conveyance of all materials to work site and other incidental charges etc., complete.		One squire metre		
4.	720.00 Cum	Cement concrete 1:5:10 (One cement five sand and ten hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.		One cubic metre		
5.	48.00 Cum	Cement concrete 1:2:4 (One cement Two sand and Four hard broken) Using 20mm ISS gauge hard broken granite stone jelly for foundation including watering wherever necessary and in layers not more than 15 cm in thick etc., including compacting and fixing the expansion joint of bitumen pad and all materials to site and all labour charges and all other including charges etc., completed.		One cubic metre		
6.	17.00 Sqm	Providing and fixing Bitumen expansion pad including cost and convince of Bitumen Pad and fixing in proper position etc., completed as per standard specification as directed by Engineer. Incharge.		One Squire metre		
7.	7.20 Cum	Spreading U.S. gravel to specified thick including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed (Road Edge packing)		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer  
Town Panchayat Works  
Annamalai Nagar.

Assistant Executive Engineer  
Town Panchayat Works  
Cuddalore Zone.