

**ந.க.எண். அ1/12/2009**

**நாள் : 20.06.2009**

**ஒப்பந்தப்புள்ளி அறிவிப்பு**

வடலூர் பேரூராட்சி அலுவலகத்தில் கீழ் கண்டுள்ள பட்டியலில் இருக்கும் பணிகளை செய்து முடிக்க மத்திய மற்றும் மாநில அரசு மற்றும் அரசு சார்ந்த நிறுவனங்களில் பதிவு பெற்ற ஒப்பந்ததாரர்களிடமிருந்து ஒப்பந்தப்புள்ளிகள் வரும் **03.07.2009 வெள்ளிக்கிழமை பிற்பகல் 3.00 மணி** வரை செயல் அலுவலர் அல்லது அவரால் அங்கீகாரம் பெற்றவரால் பெற்றுக்கொள்ளப்படும் . அவ்வாறு வரப்பெறும் ஒப்பந்தப்புள்ளிகள் அன்றைய தினமே வருகை தந்துள்ள ஒப்பந்ததாரர்கள் முன்னிலையில் **பிற்பகல் 3.30 மணிக்கு** திறந்து பதிவு செய்யப்படும். ஒப்பந்தப்புள்ளி நமூனா பெற விரும்புவோர், அதற்கான தொகையினை பேரூராட்சி அலுவலகத்தில் **02.07.2009 பிற்பகல் 5.00 மணிக்குள்** செலுத்தி பெற்றுக்கொள்ள வேண்டியது. ஒப்பந்த முன் வைப்புத் தொகை இப்பேரூராட்சி அலுவலகத்தில் தொகையாக செலுத்தப்பட வேண்டும். ஒப்பந்தப்புள்ளி நடைபெறும் நாள் அரசு விடுமுறை என அறிவிக்கப்பட்டால் மறு நாள் டெண்டர் பெற்றுக்கொள்ளப்படும்.

**பிற்படுத்தப்பட்ட மண்டலங்களுக்கான மான்ய நிதி திட்டம் 2007-2008**

வ. எண்	வேலையின் பெயர்	மதிப் பீடு (ரூ)	டேவணி தொகை (ரூ)	ஜெட்டியூல் கட்டணம் (ரூ)	வேலையை செய்து முடிக்க வேண்டிய காலம்
1.	பூசாலிக்குப்பம் மெயின் ரோடு தார்சாலை அமைத்தல் (முதல் பகுதி) (275 மீ)	260000	2600	780	60 நாட்கள்
2.	பெரிய காலனி இணைப்பு சாலை மற்றும் பி.பி.எஸ். நகர் முதல் தெரு தார்சாலை அமைத்தல் (265 மீ)	250000	2500	780	60 நாட்கள்
3.	சேராக்குப்பம் பகுதியில் நியாய விலை கடை கட்டுதல் மற்றும் அணு கு சாலை அமைத்தல் (1 எண்.)	335000	3350	780	90 நாட்கள்
4.	பார்வதிபுரம் கற்புர மேடை தெரு சிமெண்ட் சாலை அமைத்தல் (142 மீ)	275000	2750	780	30 நாட்கள்
5.	நாகப்பசாமி தெரு சிமெண்ட் சாலை அமைத்தல் (160 மீ)	310000	3100	780	30 நாட்கள்
6.	என்.எல்.சி. ஆபிசர் நகர் 7, 8 வது தெரு தார்சாலை அமைத்தல் (275 மீ)	260000	2600	780	60 நாட்கள்
7.	ஓம் சக்தி நகர் குறுக்கு தெரு சிமெண்ட் சாலை அமைத்தல் (76 மீ)	145000	1450	312	30 நாட்கள்
8.	ஆர்.சி. தோமையார் நகர் 1 மற்றும் 2வது தெரு சிமெண்ட் சாலை அமைத்தல் (169 மீ)	300000	3000	780	30 நாட்கள்
9.	வெங்கட்டங்குப்பம் பகுதி நியாய விலை கடை கட்டுதல் மற்றும் தெருவிளக்கு அமைத்தல்	315000	3150	780	90 நாட்கள்
மொத்தம்		<b>2450000</b>			

(ஓம்) நா. அர்ச்சுணன்,  
தலைவர்,  
பேரூராட்சி மன்றம்,  
வடலூர்.

(ஓம்) செ. விகவநாதன்,  
செயல் அலுவலர்,  
பேரூராட்சி அலுவலகம்,  
வடலூர்.

// உண்மை நகல் //

(ஓம்) செ. விகவநாதன்,  
செயல் அலுவலர்,  
பேரூராட்சி அலுவலகம், வடலூர்.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 3,00,000/-  
EMD Amount : Rs. 3,000/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of  
Providing Cement Concrete road @ RC Thomaiyar nagar 1,2 nd street in  
Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressly understood that the measured work is to be taken out notwithstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

**SCHEDULE - B**

**Name of work** : **Providing Cement concrete road at RC Thomaiyar nagar 1,2<sup>nd</sup> street in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs.3,00,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009**

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
1.	16.38 m3	Earthwork excavation and depositing on bank with initial lead and life as per SS20B ( for lining wall )	one cubic metre			
2.	41.59 m3	Levelling course for sand including cost and conveyance from approved quarry and labour charges for filling watering , compacting and all other incidental charges etc., completed.	one cubic metre			
3	41.59 m3	Providing and laying cement concrete 1:4:8 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying, compacting, watering and curing including all other incidental charges etc complete	one cubic metre			
4.	156.30 m2	Providing and laying cement concrete 1:5:10 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying, compacting, watering and curing including all other incidental charges etc., complete (for base concrete)	one sQaure metre			
5.	61.51 m3	Towards centering charges for concrete sides including cost of centering, all labour charges and all other incidental charges etc., completed (for lining wall)	one cubic metre			
6.	74.40 m2	Providing and laying cement concrete 1:2:4 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying and fixing the expansion joints of bitumen pad and watering curring etc., completed.	one sQaure metre			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //  
(S/d.).....  
Executive Officer,  
Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 3,15,000/-  
EMD Amount : Rs. 3,150/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of  
Construction of Fair Price Shop Building at Venkatankuppam in  
Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressively under stood that the measured work is to be taken out not withstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

## SCHEDULE - B

**Name of work** : **Construction of Fair Price Shop Building At Venkatankuppam in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs.3,15,000/-.**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009**

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
1.	41.56 m3	Earthwork excavation and depositing on bank with initial lead and life as per SS20B ( for lining wall )	one cubic metre			
2.	24.27 m3	Sand Filling with corted river sand for foundation	one cubic metre			
3	13.81 m3	Providing CC 1:4:8 mix using 40mm size HBG metal for foundation and flooring concrete 0.23 and 0.10 m thick respectively	one cubic metre			
4.	27.44 m3	Brickwork in cm 1:5 mix using good size of country bricks for footing and basement Ist and IInd floor 0.23 x 3.15 and paraper wall 0.90 high	one cubic metre			
5.	46.34 m3	RCC 1:2:4 mix using 20mm jelly for lintel, sunshade, Roof beam T Beam and Roof slab to required thickness.	one cubic metre			
6.	1400 kg	Supplying and erecting centering for sides and plave using steel centering	one kilogram			
7.	160 m2	Plastering in cm 1:4-12 mm thick for inner & outer plastering	one square metre			
8.	50 m2	Ceiling Plastering 1:3-10 mm thick	one square metre			
9.	44.10 m3	Providing Granolethic floor finish in cement concrete 1:2:4 mix using 10-12 ISS metal to 20mm thick including cost and conveyance of all materials to site and all labour charges for mixing laying curing etc complete for 10 cum	one cubic metre			

Signature of Contractor :

No of corrections :

No of overwritings :

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
10.	58.64 m2	Supplying and erecting shuttering including necessary support for plane surface in foundation and basement and in all floor for RCC columns etc complete as per standard specification.	one square metre			
11.	58.52 m2	Terrace flooring over weathering course with pressed tiles in cm 1:3 and pointed with cm 1:3 using 20x20x2 cm size including cost and conveyance of charges.	one square metre			
12.	3.00 nos	Supplying and fixing for steel door of size 1.10x2m including of all cost and conveyance and all labour charges	one number			
13.	2.00 nos	Supplying and fixing for steel window of size 0.90 x1.2m including of all cost and conveyance and all labour charges	one number			
14.	1.00 nos	Supplying and fixing for steel counter of size 0.45x 0.6m including of all cost and conveyance and all labour charges	one number			
15.	5.00 nos	Supplying and fixing for steel ventilator of size 0.60x 0.40 m including of all cost and conveyance and all labour charges	one number			
16.	160.00 m2	Distempering using two coats for mix using laying and finishing etc complete	one square metre			
17.	100.00 m2	Painting two coats mix new iron paint including cost and conveyance of paint and all labour charges etc complete	one square metre			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //

(S/d.).....

Executive Officer,  
Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 2,60,000/-  
EMD Amount : Rs. 2,600/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of BT to Poosalikuppam Main street ( I Reach ) in Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressly understood that the measured work is to be taken out notwithstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

Signature of Contractor

**SCHEDULE - B**

**Name of work** : **BT to the Poosalikuppam Main road ( I Reach ) in Vadalur Town Panchayat.**

Estimate Amount : Rs.2,60,000/-

Name of the Town Panchayat : VADALUR.

Date of Tender : 03.07.2009

Sl. No.	Qty.	Description of work	TNDSS SSRB	Unit in works	Rate in	
					Figure	Words
1	148.50 m <sup>3</sup>	Earth work excavation in all classes of soils such as hard stiffy clay, stiff black cotton , hard red earth ,shales, murram , ordinary earth , earth mixed with 50% fair sized boulders etc., with initial leads and lift including laying , spreading, levelling , sectioning,breaking clods etc., as per SS20A and all other incidental charges etc., complete as per standard specification.	one cubic metre			
2	343.75m <sup>2</sup>	Picking and existing BT surface 10 to 15 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to chamber sectioning ,levelling , etc., complete as per including labour charges for picking and other tools and plants etc., complete as per std., specification.	one sSquare metre			
3	77.34 m3	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade III using 1.00 cum of 63 mm to 11.20 mm IRC size graded hard broken granite metal with 0.24cum of gravel which shall have a P.I. value of less than 6 for blindage for 10 sqm. Of 75mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side, to departmental guage for premeasurement labour charges for spreading the metal , hand packing to camber blinding with gravel watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction , hire fuel and running charges for spreading the metal , hand packing to camber ,blinding with gravel , watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achive the specified compaction, hire , fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights, etc., complete as per standard specification for top layer ( payment shall be made for finished item of work after compaction )	one cubic metre			

Signature of Contractor :

No of corrections :

No of overwritings :

Sl. No.	Qty.	Description of work	TNDSS SSRB	Unit in works	Rate in	
					Figure	Words
4	1031.25 m <sup>2</sup>	Providing tack coat over WBM surface using 4 Kg of bitumen per 10 sqm. Inclusive of cost of bitumen including conveyance of bitumen of worksite Handling charges for the same at both ends including heating the bitumen to the required temperature labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required of bitumen including hire , fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights , flages etc.complete as per standard specification.	one sQuare metre			
5	1031.25m <sup>2</sup>	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher IRC size HBG metal 0.18 cubic meter of 13.2mm and 0.09 cubic meter of 11.2 mm with 14.60 Kg. OG bitumen for premixing for 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to work site and stacking them to departmental guage for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grade lines and profile including hire , fuel and running charges for Mini Hot mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification ( payment shall be made for finished item of work after compaction )	one sQuare metre			
6	3 nos	Towards cost and supply of 450 mm dia RCC pipe including all cost and conveyance of all charges.	one number			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //

(S/d.).....  
Executive Officer,  
Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 2,50,000/-  
EMD Amount : Rs. 2,500/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of BT to the Periya Colony Approach road, PPS nagar Ist street in Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressly understood that the measured work is to be taken out notwithstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

Signature of Contractor

**SCHEDULE - B**

**Name of work** : **BT to the Periya colony approach road, PPS nagar 1st street in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs.2,50,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009**

Sl. No.	Qty.	Description of work	TNDSS SSRB	Unit in works	Rate in	
					Figure	Words
1	143.10 m <sup>3</sup>	Earth work excavation in all classes of soils such as hard stiffy clay, stiff black cotton , hard red earth ,shales, murram , ordinary earth , earth mixed with 50% fair sized boulders etc., with initial leads and lift including laying , spreading, levelling , sectioning,breaking clods etc., as per SS20A and all other incidental charges etc., complete as per standard specification.	one cubic metre			
2	331.25 m <sup>2</sup>	Picking and existing BT surface 10 to 15 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to chamber sectioning ,levelling , etc., complete as per including labour charges for picking and other tools and plants etc., complete as per std., specification.	one square metre			
3	74.53 m <sup>3</sup>	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade III using 1.00 cum of 63 mm to 11.20 mm IRC size graded hard broken granite metal with 0.24cum of gravel which shall have a P.I. value of less than 6 for blindage for 10 sqm. Of 75mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side, to departmental guage for premeasurement labour charges for spreading the metal , hand packing to camber blinding with gravel watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction , hire fuel and running charges for spreading the metal , hand packing to camber ,blinding with gravel , watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achive the specified compaction, hire , fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights, etc., complete as per standard specification for top layer ( payment shallbe made for finished item of work after compaction )	one cubic metre			

Signature of Contractor :

No of corrections :

No of overwritings :

Sl. No.	Qty.	Description of work	TNDSS SSRB	Unit in works	Rate in	
					Figure	Words
4	993.75 m2	Providing tack coat over WBM surface using 4 Kg of bitumen per 10 sqm. Inclusive of cost of bitumen including conveyance of bitumen of worksite Handling charges for the same at both ends including heating the bitumen to the required temperature labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required of bitumen including hire , fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights , flages etc.complete as per standard specification.	one sQuare metre			
5	993.75 m2	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher IRC size HBG metal 0.18 cubic meter of 13.2mm and 0.09 cubic meter of 11.2 mm with 14.60 Kg. OG bitumen for premixing for 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to work site and stacking them to departmental guage for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grade lines and profile including hire , fuel and running charges for Mini Hot mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification ( payment shall be made for finished item of work after compaction )	one sQuare metre			
6	3 nos	Towards cost and supply of 450 mm dia RCC pipe including all cost and conveyance of all charges.	one number			

Signature of Contractor :

(S/d. ) .....  
 Junior Engineer,  
 Town Panchayat Works,  
 Vadalur.

No of corrections :

No of overwritings :

(S/d., .....)  
 Assistant Executive Engineer,  
 Town Panchayat works,  
 Cuddalore.

// True copy //  
 (S/d.).....  
 Executive Officer,  
 Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 3,35,000/-  
EMD Amount : Rs. 3,350/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of  
Construction of Fair Price Shop Building and Approach CC road at Serakuppam in  
Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressly understood that the measured work is to be taken out notwithstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

## SCHEDULE - B

**Name of work** : **Construction of Fair Price Shop Building and approach CC road at Serakuppam in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs.3,35,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009**

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
1.	41.56 m3	Earthwork excavation and depositing on bank with initial lead and life as per SS20B ( for lining wall )	one cubic metre			
2.	24.27 m3	Sand Filling with corted river sand for foundation	one cubic metre			
3	13.81 m3	Providing CC 1:4:8 mix using 40mm size HBG metal for foundation and flooring concrete 0.23 and 0.10 m thick respectively	one cubic metre			
4.	27.44 m3	Brickwork in cm 1:5 mix using good size of country bricks for footing and basement Ist and IInd floor 0.23 x 3.15 and paraper wall 0.90 high	one sQaure metre			
5.	46.34 m3	RCC 1:2:4 mix using 20mm jelly for lintel, sunshade, Roof beam T Beam and Roof slab to required thickness.	one cubic metre			
6.	1400 kg	Supplying and erecting centering for sides and plave using steel centering	one kilogram			
7.	160 m2	Plastering in cm 1:4-12 mm thick for inner & outer plastering	one sQaure metre			
8.	50 m2	Ceiling Plastering 1:3-10 mm thick	one sQaure metre			
9.	44.10 m3	Providing Granoletic floor finish in cement concrete 1:2:4 mix using 10-12 ISS metal to 20mm thick including cost and conveyance of all materials to site and all labour charges for mixing laying curing etc complete for 10 cum	one cubic metre			

Signature of Contractor :

No of corrections :

No of overwritings :

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
10.	58.64 m2	Supplying and erecting shuttering including necessary support for plane surface in foundation and basement and in all floor for RCC columns etc complete as per standard specification.	one sQaure metre			
11.	58.52 m2	Terrace flooring over weathering course with pressed tiles in cm 1:3 and pointed with cm 1:3 using 20x20x2 cm size including cost and conveyance of charges.	one sQaure metre			
12.	3.00 nos	Supplying and fixing for steel door of size 1.10x2m including of all cost and conveyance and all labour charges	one number			
13.	2.00 nos	Supplying and fixing for steel window of size 0.90 x1.2m including of all cost and conveyance and all labour charges	one number			
14.	1.00 nos	Supplying and fixing for steel counter of size 0.45x 0.6m including of all cost and conveyance and all labour charges	one number			
15.	5.00 nos	Supplying and fixing for steel ventilator of size 0.60x 0.40 m including of all cost and conveyance and all labour charges	one number			
16.	160.00 m2	Distembering using two coats for mix using laying and finishing etc complete	one sQaure metre			
17.	100.00 m2	Painting two coats mix new iron paint including cost and conveyance of paint and all labour charges etc complete	one sQaure metre			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
 Junior Engineer,  
 Town Panchayat Works,  
 Vadalur.

(S/d., .....)  
 Assistant Executive Engineer,  
 Town Panchayat works,  
 Cuddalore.

// True copy //

(S/d.).....

Executive Officer,  
 Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 2,75,000/-  
EMD Amount : Rs. 2,750/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of  
Providing Cement concrete road @ Parvathipuram Karpoora madai in  
Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressively under stood that the measured work is to be taken out not withstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

## SCHEDULE - B

**Name of work** : **Providing Cement concrete road @ Parvathipuram Karpooa madai in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs. 2,75,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009.**

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
1	25.56 m3	Earthwork excavation and depositing on bank with initial lead and life as per SS20B etc completed as per standard specification.	One cubic meter			
2	38.34 m3	Levelling course for sand including cost and conveyance from approved quarry and labour charges for filling watering , compacting and all other incidental charges etc., completed.	One cubic meter			
3	38.34m3	Providing and laying cement concrete 1:5:10 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying, compacting, watering and curing including all other incidental charges etc., complete (for base concrete)	One cubic metre			
4	191.70 m2	Towards centering charges for concrete sides including cost of centering, all labour charges and all other incidental charges etc., completed	One square meter			
5	56.86 m3	Providing and laying cement concrete 1:2:4 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying and fixing the expansion joints of bitumen pad and watering curring etc., completed.	One cubic meter			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //

(S/d.).....

Executive Officer,  
Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 3,10,000/-  
EMD Amount : Rs. 3,100/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of  
Providing Cement concrete road at Nagappa samy street in  
Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressively under stood that the measured work is to be taken out not withstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

**SCHEDULE - B**

**Name of work** : **Providing Cement concrete road @ Nagappa samy street in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs. 3,10,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009.**

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
1	28.80 m3	Earthwork excavation and depositing on bank with initial lead and life as per SS20B etc completed as per standard specification.	One cubic meter			
2	46.80 m3	Levelling course for sand including cost and conveyance from approved quarry and labour charges for filling watering , compacting and all other incidental charges etc., completed.	One cubic meter			
3	46.80 m3	Providing and laying cement concrete 1:5:10 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying, compacting, watering and curing including all other incidental charges etc., complete (for base concrete)	One cubic metre			
4	216.00 m2	Towards centering charges for concrete sides including cost of centering, all labour charges and all other incidental charges etc., completed	One square meter			
5	67.08 m3	Providing and laying cement concrete 1:2:4 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying and fixing the expansion joints of bitumen pad and watering curring etc., completed.	One cubic meter			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //

(S/d.).....

Executive Officer,  
Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 2,60,000/-  
EMD Amount : Rs. 2,600/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of BT to NLC officers nagar 7,8<sup>th</sup> street in Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressly understood that the measured work is to be taken out notwithstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

**SCHEDULE - B**

**Name of work** : **BT to the NLC officers nagar 7, 8<sup>th</sup> street in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs.2,60,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009**

Sl. No.	Qty.	Description of work	TNDSS SSRB	Unit in works	Rate in	
					Figure	Words
1	148.50 m <sup>3</sup>	Earth work excavation in all classes of soils such as hard stiffy clay, stiff black cotton , hard red earth ,shales, murram , ordinary earth , earth mixed with 50% fair sized boulders etc., with initial leads and lift including laying , spreading, levelling , sectioning,breaking clods etc., as per SS20A and all other incidental charges etc., complete as per standard specification.	one cubic metre			
2	343.70 m <sup>2</sup>	Picking and existing BT surface 10 to 15 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to chamber sectioning ,levelling , etc., complete as per including labour charges for picking and other tools and plants etc., complete as per std., specification.	one sSquare metre			
3	77.34 m3	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade III using 1.00 cum of 63 mm to 11.20 mm IRC size graded hard broken granite metal with 0.24cum of gravel which shall have a P.I. value of less than 6 for blindage for 10 sqm. Of 75mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side, to departmental guage for premeasurement labour charges for spreading the metal , hand packing to camber blinding with gravel watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction , hire fuel and running charges for spreading the metal , hand packing to camber ,blinding with gravel , watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achive the specified compaction, hire , fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights, etc., complete as per standard specification for top layer ( payment shallbe made for finished item of work after compaction )	one cubic metre			

Signature of Contractor :

No of corrections :

No of overwritings :

Sl. No.	Qty.	Description of work	TNDSS SSRB	Unit in works	Rate in	
					Figure	Words
4	1031.25 m2	Providing tack coat over WBM surface using 4 Kg of bitumen per 10 sqm. Inclusive of cost of bitumen including conveyance of bitumen of worksite Handling charges for the same at both ends including heating the bitumen to the required temperature labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required of bitumen including hire , fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights , flages etc.complete as per standard specification.	one sSquare metre			
5	1031.25 m2	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher IRC size HBG metal 0.18 cubic meter of 13.2mm and 0.09 cubic meter of 11.2 mm with 14.60 Kg. OG bitumen for premixing for 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to work site and stacking them to departmental guage for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grade lines and profile including hire , fuel and running charges for Mini Hot mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification ( payment shall be made for finished item of work after compaction )	one sSquare metre			
6	3 nos	Towards cost and supply of 450 mm dia RCC pipe including all cost and conveyance of all charges.	one number			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //

(S/d.).....  
Executive Officer,  
Town Panchayat, VADALUR.

**VADALUR TOWN PANCHAYAT**  
**TENDER SCHEDULE**

Issued to Thiru/Tmt-----

Estimate Amount : Rs. 1,45,000/-  
EMD Amount : Rs. 1,450/-  
Tender Date : 03.07.2009

Executive officer,  
Vadalur Town Panchayat.

**Schedule of Quantities rates and approximate quantities to accompany the tender for the work of  
Providing Cement concrete road @ Om sakthi nagar cross road in  
Vadalur Town Panchayat.**

**SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressively under stood that the measured work is to be taken out not withstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

**Signature of Contractor**

**SCHEDULE - B**

**Name of work** : **Providing Cement concrete road @ Om sakthi nagar cross road in Vadalur Town Panchayat.**

**Estimate Amount** : **Rs. 1,45,000/-**

**Name of the Town Panchayat** : **VADALUR.**

**Date of Tender** : **03.07.2009.**

Item no	Probable Quantity	Description of work	Units in Words	SSRB/MOST	Rate quoted	
					In figure	In words
1	13.68 m3	Earthwork excavation and depositing on bank with initial lead and life as per SS20B etc completed as per standard specification.	One cubic meter			
2	22.17 m3	Levelling course for sand including cost and conveyance from approved quarry and labour charges for filling watering , compacting and all other incidental charges etc., completed.	One cubic meter			
3	22.17 m3	Providing and laying cement concrete 1:5:10 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying, compacting, watering and curing including all other incidental charges etc., complete (for base concrete)	One cubic metre			
4	102.60 m2	Towards centering charges for concrete sides including cost of centering, all labour charges and all other incidental charges etc., completed	One square meter			
5	31.85 m3	Providing and laying cement concrete 1:2:4 mix using 40mm ISS HBG metal including cost and conveyance of all materials from approved quarry including labour for mixing concrete, laying and fixing the expansion joints of bitumen pad and watering curring etc., completed.	One cubic meter			

Signature of Contractor :

No of corrections :

No of overwritings :

(S/d. ) .....  
Junior Engineer,  
Town Panchayat Works,  
Vadalur.

(S/d., .....)  
Assistant Executive Engineer,  
Town Panchayat works,  
Cuddalore.

// True copy //

(S/d.).....

Executive Officer,  
Town Panchayat, VADALUR.