

## ஒப்பந்தப்புள்ளி விளம்பரம்

1. புவனகிரி பேரூராட்சி பகுதியில் அட்டவணையில் குறிப்பிட்டுள்ள வேலையை செய்து முடிப்பதற்கான மூடி முத்திரையிடப்பட்ட குறுகியகால ஒப்பந்தப்புள்ளிகள் பதிவுசெய்த ஒப்பந்தாரரிடமிருந்து பேரூராட்சி செயல் அலுவலர் அல்லது அலுவலரது அங்கீகாரம் பெற்றவரால் 06.12.2007 வியாழக்கிழமை பிற்பகல் 3.00 மணி வரை பேரூராட்சி அலுவலகத்தில் பெற்றுக் கொள்ளப்படும்.
2. ஒப்பந்தப்புள்ளிகள் புவனகிரி பேரூராட்சி செயல் அலுவலர் அவர்களின் முகவரிக்கு அனுப்பப்பட வேண்டும். உறையின் மீது எந்த வேலைக்கான ஒப்பந்தப்புள்ளிகள் என்பதை தெளிவாக குறிப்பிட வேண்டும்.
3. அட்டவணையில் குறிப்பிட்டுள்ள வேலைக்குரிய டேவணித் தொகையினை 06.12.2007 வியாழக்கிழமை அன்று பிற்பகல் 2.00 மணிக்கு அலுவலகத்தில் ரொக்கமாக செலுத்தி இரசீது பெற்று ஒப்பந்தப்புள்ளியுடன் இணைத்து அனுப்பப்பட வேண்டும்.
4. ஒப்பந்தப்புள்ளிகள் அட்டவணை ஒப்பந்தப்புள்ளி அடிப்படையில் கோரப்படுகிறது. எனவே, அட்டவணை ஒப்பந்தப்புள்ளி நமூனாக்கள் பேரூராட்சி அலுவலகத்தில் 05.12.2007 புதன்கிழமை மாலை 5.00 மணி வரையில் வழங்கப்படும். அதற்கான தொகையை அட்டவணையில் குறிப்பிட்டுள்ளபடி செலுத்தி பெற்றுக் கொள்ளலாம்.
5. காலம் தவறி வரும் ஒப்பந்தப்புள்ளிகள், முழுமையாக பூர்த்தி செய்யப்படாத ஒப்பந்தப்புள்ளிகள் நிராகரிக்கப்படும்.
6. மூடி முத்திரையிடப்படாத ஒப்பந்தப்புள்ளிகள் ஏற்றுக்கொள்ளப்பட மாட்டாது.
7. பணவரம்பு உள்ளவர்கள் மட்டுமே டேவணித் தொகையை செலுத்தி ஒப்பந்தப்புள்ளிகள் கொடுக்க வேண்டும்.
8. பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் ஆஜராகியுள்ள ஒப்பந்ததாரர்கள் முன்னிலையில் (06.12.2007) வியாழக்கிழமை பிற்பகல் 3.30 மணிக்கு திறக்கப்படும்.
9. அங்கீகரிக்கப்பட்ட ஒப்பந்தப்புள்ளிகளுக்கு ஒப்பந்ததாரர்கள் இலாகா சம்மந்தப்பட்ட சட்டதிட்டங்களுக்கு கட்டுப்பட்டு வேலையினை செய்து முடிப்பதற்காக ரூ20.00 மதிப்புள்ள முத்திரைத்தாளில் எழுத்து மூலமாக ஒப்பந்தம் செய்து கொடுக்க வேண்டும்.
10. ஒப்பந்தம் செய்யப்பட்ட வேலையினை ஒப்பந்ததாரரே செய்து முடிக்க வேண்டும். கீழ்க்குத்தகைக்கு விடக்கூடாது.
11. ஒப்பந்ததாரர் செயல் அலுவலர் குறிப்பிடும் இடத்திலிருந்து இலாகா மூலம் வழங்கும், வேலைக்கான பொருட்களை பெற்றுக் கொள்ள வேண்டும்.
12. இலாக்கா மூலம் வழங்கப்படும் பொருட்களுக்கு ஒப்பந்த நமூனாவில் குறிப்பிட்டுள்ள உரிய கிரயத்தொகை பிடித்தம் செய்யப்படும்.

13. வேலையினை அதன் எதிரே குறிப்பிட்டுள்ள காலத்திற்குள்செய்துமுடிக்க வேண்டும் தவறினால் வைப்புத் தொகையினை பறிமுதல் செய்யப்படுவதுடன் அறிவிப்பு ஏதுமின்றி ஒப்பந்தம் ரத்து செய்யப்படும். அதனால் ஏற்படும் சகல நஷ்டங்களுக்கும் ஒப்பந்ததாரரே பொறுப்பாவார்.
14. தணிக்கை முடிவுபெற்ற பின்னர் தணிக்கையில் ஆட்சேபனை இருப்பின், ஆட்சேபனை நிவர்த்தி செய்யப்பட்டபிறகே பட்டியலில் பிடித்தம் செய்யப்பட்ட தொகை மீள வழங்கப்படும்.
15. கீழ் கண்ட திட்டப் பணிகளுக்கு அரசிடமிருந்து நிதி ஒதுக்கீடு பெறப்பட்ட பின்னரே தொகை பட்டுவாடா செய்யப்படும்.
16. இதர விபரங்களை அலுவலகத்தில் அலுவலக நேரங்களில் விசாரித்து தெரிந்துகொள்ளலாம்.

**2007-2008 -ம் ஆண்டில் நிறைவேற்றப்படவுள்ள  
சட்டமன்ற உறுப்பினர் தொகுதி மேம்பாடு திட்டப்பணிகள் விபரம்  
அட்டவணை**

வ. எண்	வேலையின் விபரம்	மதிப்பீடு தொகை ரூ (இலட்சத்தில்)	டேவணித் தொகை ரூ	ஒப்பந்த நழுனா ரூ	பணி முடிக்கப்பட வேண்டிய காலம்
1.	தாமரைக்குளத்தெரு சிமெண்ட் சாலைப்பணி	1.50	1500/-	672/-	உத்திரவு கிடைக்கப் பெற்ற 60 தினங்களுக்குள்
2.	சுந்தரமாரியம்மன் கோயில் தெரு தார்சாலைப்பணி	1.50	1500/-	672/-	உத்திரவு கிடைக்கப் பெற்ற 60 தினங்களுக்குள்
3.	கள்ளிக்காட்டுத்தெரு செட்டிக்குளம் ஆ.தி தெரு தார்சாலைப்பணி	1.50	1500/-	672/-	உத்திரவு கிடைக்கப் பெற்ற 60 தினங்களுக்குள்
4.	ஈஸ்வரன் கோயில் தெரு தார்சாலைப்பணி	1.50	1500/-	672/-	உத்திரவு கிடைக்கப் பெற்ற 60 தினங்களுக்குள்

பெறுதல்:-

பேரூராட்சியில் பதிவு பெற்ற ஒப்பந்ததாரர்கள்

செயல் அலுவலர்

பேரூராட்சி அலுவலகம்

புவனகிரி - 608 601.

நகல்:-

1. தலைவர், துணைத்தலைவர் மற்றும் உறுப்பினர்கள், பேரூராட்சி மன்றம், புவனகிரி.
2. பேரூராட்சிகளின் உதவி இயக்குநர், கடலூர் மண்டலம், கடலூர் அவர்களுக்கு தகவலறிய பணிந்து அனுப்பப்படுகிறது.
3. உதவி செயற் பொறியாளர், பேரூராட்சிகளின் உதவி இயக்குநர் அலுவலகம், கடலூர் அவர்களுக்கு தகவலறிய பணிந்து அனுப்பப்படுகிறது.
4. உதவிப்பொறியாளர், பேரூராட்சி பணிகள், பேரூராட்சி அலுவலகம், அண்ணாமலை நகர் அவர்களுக்கு தகவலறிய அனுப்பப்படுகிறது.
5. விளம்பரப் பலகைக்கு.

**SCHEDULE-A**

**Name Of The Work :** Providing Cement Concrete Road @ Thamarai Kulam School Street  
in Bhuvanagiri Town Panchayat.

**Estimate Cost :** 1,50,000/-

**Date Of Tender :** 06.12.2007

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
1	15.00 m <sup>3</sup>	Earth work excavation and deposition an bank within initial lead and lift as per SS 20 B for lining wall		One cubic meter		
2	15.00 m <sup>3</sup>	Sand filling with good river sand from approved quarry including cost and conveyance of materials and all labour charges etc for leveling course		One cubic meter		
3	24.00 m <sup>3</sup>	P.C.C.1:4:8 mixing 40mm ISS HBG metal including cost and conveyance to site and all charges, for base course		One Cubic Meter		
4	108.00 m <sup>2</sup>	Centering for soffits of cement concrete for sides including strutting and all labour charges etc., for sides		One Squire Meter		
5	11.00 m <sup>3</sup>	P.C.C.1:3:6 mixing 20mm ISS HBG metal including cost and conveyance to site and all charges, for base course		One cubic meter		
6	24.00 m <sup>3</sup>	P.C.C.1:2:4 mixing 20mm ISS HBG metal including cost and conveyance to site and all charges, for top course		One cubic meter		

Signature of Contractor:

S/d xxxxxxxxxxxxxxxx  
Assistant Engineer  
Town Panchayat works,  
Annamalai Nagar.

No.of Corrections:

No.of Overwriting:

S/d xxxxxxxxxxxxxxxx  
Assistant Executive Engineer  
Town Panchayat works,  
Cuddalore District.

**SCHEDULE-A**

**Name Of The Work :** Providing Premix carpet with Seal Coat @ Sundaramariyamman koil Street  
in Bhuvanagiri Town Panchayat.

**Estimate Cost :** 1,50,000/-

**Date Of Tender :** 06.12.2007

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
1	375.00 m <sup>2</sup>	<b>Picking and existing WBM</b> surface 3 to 5 cm deep removed of picked up stuff to the side beams and using the useful metal to the road hand packing to chamber sectioning, leveling, etc. complete us per including labour charges for picking and other tools and plants etc. completed as per standard specification.		One Squire Meter		
2	36.00 m <sup>3</sup>	Providing and laying thickness of water Bound Macadam conforming to <b>Grade -II</b> using 1.00 cum of (90 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc.		One cubic meter		
3	36.00 m <sup>3</sup>	Providing and laying thickness of water Bound Macadam conforming to <b>Grade -III</b> using 1.00 cum of (63 mm to 11.20 mm) IRC size graded hard broken granite metal with 0.24 cum of gravel for blind age, 75 mm Consolidated thickness, including cost and conveyance of metal and gravel and labour charges for spreading the metal consolidating using power roller, hire charges and all other incidental charges etc. completed,		One Cubic Meter		

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
4	469.00 m <sup>2</sup>	Providing <b>Tack coat over WBM surface</b> using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen section store and the cost of at department section store and the cost of which will be recovered at the rate as specified in the special condition appended here with including conveyance of bitumen from section store to worksite handling charges for the same at both ends including heating the bitumen to the required temperature labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One Squire Meter		
5	469.00 m <sup>2</sup>	Providing and laying <b>premix carpet with seal coat</b> type A for 20 mm consolidated thickness using machine crusher IRC size HBG metal 0.18 cubic meter of 13.2mm and 0.09 cubic meter of 11.2 mm with 14.60 kg, Of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.75 mm IRC HBG crusher metal with 9.80 kg of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges completed		One Squire Meter		

Signature of Contractor:

No.of Corrections:

No.of Overwriting:

S/d xxxxxxxxxxxxxxxx  
Assistant Engineer  
Town Panchayat works,  
Annamalai Nagar,

S/d xxxxxxxxxxxxxxxx  
Assistant Executive Engineer  
Town Panchayat works,  
Cuddalore District.

**SCHEDULE-A**

**Name Of The Work :** Providing Premix carpet with Seal Coat @ Kallikkattu Street Settikulam road in Bhuvanagiri Town Panchayat.

**Estimate Cost :** 1,50,000/-

**Date Of Tender :** 06.12.2007

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
1	432.00 m <sup>2</sup>	<b>Picking and existing WBM</b> surface 3 to 5 cm deep removed of picked up stuff to the side beams and using the useful metal to the road hand packing to chamber sectioning, leveling, etc. complete us per including labour charges for picking and other tools and plants etc. completed as per standard specification.		One Squire Meter		
2	35.00 m <sup>3</sup>	Providing and laying thickness of water Bound Macadam conforming to <b>Grade -II</b> using 1.00 cum of (90 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc.		One cubic meter		
3	35.00 m <sup>3</sup>	Providing and laying thickness of water Bound Macadam conforming to <b>Grade -III</b> using 1.00 cum of (63 mm to 11.20 mm) IRC size graded hard broken granite metal with 0.24 cum of gravel for blind age, 75 mm Consolidated thickness, including cost and conveyance of metal and gravel and labour charges for spreading the metal consolidating using power roller, hire charges and all other incidental charges etc. completed,		One Cubic Meter		

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
4	460.00 m <sup>2</sup>	Providing <b>Tack coat over WBM surface</b> using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen section store and the cost of at department section store and the cost of which will be recovered at the rate as specified in the special condition appended here with including conveyance of bitumen from section store to worksite handling charges for the same at both ends including heating the bitumen to the required temperature labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One Squire Meter		
5	460.00 m <sup>2</sup>	Providing and laying <b>premix carpet with seal coat</b> type A for 20 mm consolidated thickness using machine crusher IRC size HBG metal 0.18 cubic meter of 13.2mm and 0.09 cubic meter of 11.2 mm with 14.60 kg, Of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.75 mm IRC HBG crusher metal with 9.80 kg of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges completed		One Squire Meter		

Signature of Contractor:

No.of Corrections:

No.of Overwriting:

S/d xxxxxxxxxxxxxxxx  
Assistant Engineer  
Town Panchayat works,  
Annamalai Nagar,

S/d xxxxxxxxxxxxxxxx  
Assistant Executive Engineer  
Town Panchayat works,  
Cuddalore District.

**SCHEDULE-A**

**Name Of The Work :** Providing Premix carpet with Seal Coat @ Eswarankoil Street (Main road lane)  
in Bhuvanagiri Town Panchayat.

**Estimate Cost :** 1,50,000/-

**Date Of Tender :** 06.12.2007

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
1	345.00 m <sup>2</sup>	<b>Picking and existing WBM</b> surface 3 to 5 cm deep removed of picked up stuff to the side beams and using the useful metal to the road hand packing to chamber sectioning, leveling, etc. complete us per including labour charges for picking and other tools and plants etc. completed as per standard specification.		One Squire Meter		
2	35.00 m <sup>3</sup>	Providing and laying thickness of water Bound Macadam conforming to <b>Grade -II</b> using 1.00 cum of (90 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc.		One cubic meter		
3	35.00 m <sup>3</sup>	Providing and laying thickness of water Bound Macadam conforming to <b>Grade -III</b> using 1.00 cum of (63 mm to 11.20 mm) IRC size graded hard broken granite metal with 0.24 cum of gravel for blind age, 75 mm Consolidated thickness, including cost and conveyance of metal and gravel and labour charges for spreading the metal consolidating using power roller, hire charges and all other incidental charges etc. completed,		One Cubic Meter		

Item No.	Probable Quantity	Description of Work	SSRB / MOST	Unit in Words	Rate In	
					Figure	Words
1	2	3	4	5	6	7
	460.00 m <sup>2</sup>	Providing <b>Tack coat over WBM surface</b> using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen section store and the cost of at department section store and the cost of which will be recovered at the rate as specified in the special condition appended here with including conveyance of bitumen from section store to worksite handling charges for the same at both ends including heating the bitumen to the required temperature labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One Squire Meter		
	460.00 m <sup>2</sup>	Providing and laying <b>premix carpet with seal coat</b> type A for 20 mm consolidated thickness using machine crusher IRC size HBG metal 0.18 cubic meter of 13.2mm and 0.09 cubic meter of 11.2 mm with 14.60 kg, Of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.75 mm IRC HBG crusher metal with 9.80 kg of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges completed		One Squire Meter		

Signature of Contractor:

No.of Corrections:

No.of Overwriting:

S/d xxxxxxxxxxxxxxxxx  
Assistant Engineer  
Town Panchayat works,  
Annamalai Nagar,

S/d xxxxxxxxxxxxxxxxx  
Assistant Executive Engineer  
Town Panchayat works,  
Cuddalore District.