

**காட்டுமன்னார்கோயில் பேரூராட்சியின் குறுகிய கால
ஒப்பந்தப்புள்ளி விளம்பரம்**

ந.க.எண்.அ1/275/2007

நாள் : 10.01.2008

- காட்டுமன்னார்கோயில் பேரூராட்சி பகுதியில் அட்டவணையில் குறிப்பிட்டுள்ள வேலையினை செய்து முடிப்பதற்கான மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகளை இப்பேரூராட்சியில் பதிவு செய்த ஒப்பந்ததாரர்களிடமிருந்து பேரூராட்சி செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் 25-01-2008 வெள்ளிக்கிழமை பிற்பகல் 3.00 மணி வரை பேரூராட்சி அலுவலகத்தில் பெற்றுக்கொள்ளப்படும்.
- ஒப்பந்தப்புள்ளிகளை காட்டுமன்னார்கோயில் பேரூராட்சி செயல் அலுவலர் அவர்களின் முகவரிக்கு அனுப்பப்படவேண்டும். உரையின்மீது எந்த வேலைக்கான ஒப்பந்தப்புள்ளிகள் என்பதை தெளிவாக குறிப்பிடவேண்டும்.
- அட்டவணையில் குறிப்பிட்டுள்ளபடி வேலைக்குரிய டேவணித்தொகையினை அலுவலக நேரத்திற்குள் பேரூராட்சி அலுவலகத்தில் ரொக்கமாக செலுத்தி இரகீது பெற்று ஒப்பந்தப்புள்ளியுடன் இணைத்து அனுப்பப்படவேண்டும்.
- ஒப்பந்தப்புள்ளி அட்டவணை அடிப்படையில் கோரப்படுகிறது. எனவே, ஒப்பந்தப்புள்ளி நமூனாக்கள் பேரூராட்சி அலுவலகத்தில் 24-01-2008- ந்தேதி **வியாழக்கிழமை** பிற்பகல் 2.00 மணி வரை வழங்கப்படும். அதற்கான தொகை ஒவ்வொரு பணிக்கும் அதன் எதிரே கண்டுள்ள தொகையினை செலுத்தி பெற்றுக்கொள்ளலாம்.
- காலம் தவறி வரும் ஒப்பந்தப்புள்ளிகள் மற்றும் முழுமையாக பூர்த்தி செய்யப்படாத ஒப்பந்தப்புள்ளிகள் ஒப்பந்த வைப்பு செலுத்தாத ஒப்பந்தப்புள்ளிகள் நிராகரிக்கப்படும்.
- மூடி முத்திரையிடப்படாத ஒப்பந்தப்புள்ளிகள் ஏற்றுக்கொள்ளப்பட மாட்டாது.
- பண வரம்பு உள்ளவர்களுக்கு மட்டுமே டேவணித்தொகையை செலுத்தி ஒப்பந்தப்புள்ளி கொடுக்க வேண்டும்.
- பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் ஆஜராகியுள்ள ஒப்பந்ததாரர் முன்னிலையில் 25-01-2008 தேதி **வெள்ளிக் கிழமை** பிற்பகல் 3.30 மணிக்கு திறக்கப்படும்.
- அங்கீகரிக்கப்பட்ட ஒப்பந்தப்புள்ளி ஒப்பந்ததாரர்கள் இலாகா சம்மந்தப்பட்ட சட்டதிட்டங்களுக்கு கட்டுப்பட்டு வேலையினை செய்து முடிப்பதற்காக ரூ.20/- மதிப்புள்ள முத்திரைத்தாளில் எழுத்து மூலமாக ஒப்பந்தம் செய்து கொடுக்க வேண்டும்.
- ஒப்பந்தம் செய்யப்பட்ட வேலையினை ஒப்பந்ததாரரே செய்து முடிக்க வேண்டும். கீழ் குத்தகைக்கு விடக்கூடாது.
- வேலையினை அதன் எதிரே குறிப்பிட்டுள்ள காலத்திற்குள் செய்து முடிக்க வேண்டும். தவறினால் வைப்புத்தொகையினை பறிமுதல் செய்வதுடன் முன் அறிவிப்பு ஏதுமின்றி ஒப்பந்தம் ரத்து செய்யப்படும். அதனால் ஏற்படும் சகல நஷ்டங்களுக்கும் ஒப்பந்ததாரரே பொறுப்பாவார்.
- ஒப்பந்ததாரர் வேலைக்கான உத்திரவு கிடைத்தவுடன் ஒரு வார காலத்திற்குள் வேலை ஆரம்பிக்கப்பட வேண்டும். தவறினால் ஒப்பந்ததாரர் பதிவு ரத்து செய்யப்படும்.
- நிர்வாக காரணங்களுக்காக ஒப்பந்தத்தை எந்த முன் அறிவிப்பின்மீது ஒத்திவைக்கவும், நீக்கிடவும் செயல் அலுவலருக்கு முழு அதிகாரம் உண்டு.
- மதிப்பீடு 5.00 லட்சத்திற்கு மேலுள்ள பணிகளை இணையதளத்தில் செயல் அலுவலர், பேரூராட்சி அலுவலகத்தில் நமூனா டவுன்லோடு செய்து பெற்றுக்கொள்ளலாம். அதற்குரிய டெண்டர் நமூனா தொகையினை வங்கி வரைவு பெற்று டெண்டர் நமூனாவில் இணைக்கப்படவேண்டும். (ஒப்பந்தப்புள்ளி விளம்பரம் தேதிப்படி)

(த.பி.பா)

சட்டமன்ற உறுப்பினர் மேம்பாடுத்திட்டம் (MLA - Scheme) 2007-2008

வ. எண்	பணியின் பெயர்	நீளம்/ எண்ணி -க்கை	மதிப்பீடு (இலட்சம்)	டெண்டர் நமூனா	டேவணித் தொகை	பணி முடிக்க வேண்டிய காலம்
1	கோலியர் தெருவில் (மின்வாரிய அலுவலகம் அருகில்) தார்சாலை அமைத்தல்	205 மீ	3.00	1676	3000	60 நாட்கள்

செயல் அலுவலர்
பேரூராட்சி அலுவலகம்
காட்டுமன்னார்கோயில்.

நகல்-

- பேரூராட்சியின் பதிவு பெற்ற ஒப்பந்ததாரர்கள்
- திட்ட அலுவலர் அவர்கள், மாவட்ட ஊரக வளர்ச்சி முகமை கடலூர் அவர்களுக்கு தகவலுக்காக பணிந்தனுப்பப்படுகிறது.
- பேரூராட்சிகளின் உதவி இயக்குநர், கடலூர் அவர்களுக்கு தகவலுக்காக பணிந்தனுப்பப்படுகிறது.
- உதவி செயற்பொறியாளர், பேரூராட்சி பணிகள் உதவி இயக்குநர் அலுவலகம், கடலூர் அவர்களுக்கு தகவலுக்காக அனுப்பப்படுகிறது.
- இளநிலை பொறியாளர், பேரூராட்சி அலுவலகம், அண்ணாமலைநகர் அவர்களுக்கு தகவலுக்காக
- சட்டமன்ற தொகுதி உறுப்பினர் அவர்கள், காட்டுமன்னார்கோயில் சட்டமன்ற தொகுதி, காட்டுமன்னார்கோயில்
- தலைவர், துணைத்தலைவர் மற்றும் உறுப்பினர்கள் பேரூராட்சி , காட்டுமன்னார்கோயில் தகவலறிய
- காட்டுமன்னார்கோயில் பேரூராட்சி எல்லைக்குட்பட்ட அலுவலகங்கள்
- காட்டுமன்னார்கோயில் பேரூராட்சி அலுவலக தகவல் பலகைக்கு

SCHEDULE - A

NAME OF WORK : PROVIDING PREMIX CARPET WITH SEAL COAT @ KOLIYAR STREET NEAR E.B.OFFICE IN KATTUMANNARKOIL TOWN PANCHAYAT

NAME OF TOWN PANCHAYAT : KATTUMANNARKOIL

DATE OF TENDER :

ESTIMATE COST :3,00,000/-

SOLD TO :

Item No. 1	Probable Quantity 2.	Description of Work 3.	SSRB/M OST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1	333.00 cum	Earth work excavation in all classes of soils such as hard stiff clay, stiff black cotton, hard red earth, shales, murrum, ordinary earth, earth mixed with 50 % fair-sized boulders etc., with initial leads and lift including laying, spreading, leveling, sectioning, breaking clods etc., as per SS 20 A and all other incidental charges etc., complete as per standard specification.	SSRB 301-310	One cubic metre		
2	28.00cum	Providing and laying U.S gravel to the specified thick including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick (or) as specified by the departmental officer, leveling, sectioning etc. and all other charges for tools and plants employed for the work and all other incidental charges such as barricading and providing danger lights etc; complete as per standard specification.				
3	615sqm	Picking the existing Worn tout Surface 3 to 5 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to camber sectioning, leveling, etc., complete as per including labour charges for picking and other tools and plants etc., complete as per standard specification.				

4	47.00 cum	Providing and laying water bound macadam to a consolidated thickness of 75 mm conforming to Grade II using 1.00 cm 73 mm to 45 mm IRC graded hard broken granite metal with 0.24 cum of gravel which shall have P.I. value of less than 6 for blindage for 10 sqm of 75 mm consolidated thickness including cost and conveyance of metal and gravel from approved quarry to worksite and stacking them at road side to departmental gauge for premeasurement labour charges for spreading the metal, and hand packing to camber blinding with gravel watering, with all leads for soft water forming edge bunds slurring consolidating using power roller to achieve the specified compaction including hire fuel and all other tools and plants employed and all other incidental charges such as barricading providing danger lights etc., complete as per standard specification for Bottom layer.				
5	47.00 cum	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade - III using 1.00 cum. Of 53 mm to 22.4 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blindage for 10 sqm. 0. 75 mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement, labour charges for spreading the metal, hand packing to camber, blinding with gravel, watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller and all othe tools and plants employed and all other incidental charges such as barricading, providing danger lights etc., complete as per standard specification, for Top layer (payment shall be made for finished item of work after compaction).				
6	615.00 cum	Providing tack coat over W.B.M. surface using 10 kg of bitumen per 10 sqm inclusive of cost of bitumen which will be supplied departmentally at departmental section store and the cost of which will be recovered at the rate as specified in the special condition appended here with including conveyance of bitumen from section store to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour fro applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is				

		employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.				
7	615.00 cum	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre fo 13.s mm and 0.09 cubic metre of 11.2 mm with 14.60 kg of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. for seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows ncluding labour charges for spreading te mix to grades lines and profile and consolidation with power roller rolling etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).				
8	18.00 cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stoney each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus each as shown by the departmental officers at site as per standard specifications.				
9	6.00cum	Sanfilding with dry with river sand including all Labour charges etc completed				

	101.00 sqm	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including cost and conveyance of all materials to site and all other incidental charges etc., complete.				
	19.00 sqm	Cement concrete 1:3:6 (One cement three sand and Six hard broken stone) using 20mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of Materials at site and labour charges complete complying with standard specifications. Kerbwall				
	12.00 cum	Cement concrete 1:4:8 (One cement four sand and Eight hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.				

Signature of Contractor

No. of corrections :
No.of overwritings:

Junior Engineer
Town Panchayat
Annamalainagar

Assistant Executive Engineer
Town Panchayat Works
Cuddalore.