

**காட்டுமன்னார்கோயில் பேரூராட்சியின் குறுகிய கால
ஒப்பந்தப்புள்ளி விளம்பரம்**

ந.க.எண்.அ1 / 224 / 2007

நாள் : 18.01.2008

- காட்டுமன்னார்கோயில் பேரூராட்சி பகுதியில் அட்டவணையில் குறிப்பிட்டுள்ள வேலையினை செய்து முடிப்பதற்கான மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகளை இப்பேரூராட்சியில் பதிவு செய்த ஒப்பந்ததாரர்களிடமிருந்து பேரூராட்சி செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் **31-01-2008 வியாழக் கிழமை** பிற்பகல் 3.00 மணி வரை பேரூராட்சி அலுவலகத்தில் பெற்றுக்கொள்ளப்படும்.
- ஒப்பந்தப்புள்ளிகளை காட்டுமன்னார்கோயில் பேரூராட்சி செயல் அலுவலர் அவர்களின் முகவரிக்கு அனுப்பவேண்டும். உரையின்மீது எந்த வேலைக்கான ஒப்பந்தப்புள்ளிகள் என்பதை தெளிவாக குறிப்பிடவேண்டும்.
- அட்டவணையில் குறிப்பிட்டுள்ளபடி வேலைக்குரிய டேவணித்தொகையினை அலுவலக நேரத்திற்குள் பேரூராட்சி அலுவலகத்தில் ரொக்கமாக செலுத்தி இரசீது பெற்று ஒப்பந்தப்புள்ளியுடன் இணைத்து அனுப்பப்படவேண்டும்.
- ஒப்பந்தப்புள்ளி அட்டவணை அடிப்படையில் கோரப்படுகிறது. எனவே, ஒப்பந்தப்புள்ளி நமூனாக்கள் பேரூராட்சி அலுவலகத்தில் **30-01-2008- ந்தேதி புதன்கிழமை** பிற்பகல் 2.00 மணி வரை வழங்கப்படும். அதற்கான தொகை ஒவ்வொரு பணிக்கும் அதன் எதிரே கண்டுள்ள தொகையினை செலுத்தி பெற்றுக்கொள்ளலாம்.
- காலம் தவறி வரும் ஒப்பந்தப்புள்ளிகள் மற்றும் முழுமையாக பூர்த்தி செய்யப்படாத ஒப்பந்தப்புள்ளிகள் ஒப்பந்த வைப்பு செலுத்தாத ஒப்பந்தப்புள்ளிகள் நிராகரிக்கப்படும்.
- மூடி முத்திரையிடப்படாத ஒப்பந்தப்புள்ளிகள் ஏற்றுக்கொள்ளப்பட மாட்டாது.
- பண வரம்பு உள்ளவர்களுக்கு மட்டுமே டேவணித்தொகையை செலுத்தி ஒப்பந்தப்புள்ளி கொடுக்க வேண்டும்.
- பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் ஆஜராகியுள்ள ஒப்பந்ததாரர் முன்னிலையில் **31-01-2008 தேதி வியாழக் கிழமை** பிற்பகல் 3.30 மணிக்கு திறக்கப்படும்.
- அங்கீகரிக்கப்பட்ட ஒப்பந்தப்புள்ளி ஒப்பந்ததாரர்கள் இலாகா சம்மந்தப்பட்ட சட்டதிட்டங்களுக்கு கட்டுப்பட்டு வேலையினை செய்து முடிப்பதற்காக ரூ.20/- மதிப்புள்ள முத்திரைத்தாளில் எழுத்து மூலமாக ஒப்பந்தம் செய்து கொடுக்க வேண்டும்.
- ஒப்பந்தம் செய்யப்பட்ட வேலையினை ஒப்பந்ததாரரே செய்து முடிக்க வேண்டும். கீழ் குத்தகைக்கு விடக்கூடாது.
- வேலையினை அதன் எதிரே குறிப்பிட்டுள்ள காலத்திற்குள் செய்து முடிக்க வேண்டும். தவறினால் வைப்புத்தொகையினை பறிமுதல் செய்வதுடன் முன் அறிவிப்பு ஏதுமின்றி ஒப்பந்தம் ரத்து செய்யப்படும். அதனால் ஏற்படும் சகல நஷ்டங்களுக்கும் ஒப்பந்ததாரரே பொறுப்பாவார்.
- ஒப்பந்ததாரர் வேலைக்கான உத்திரவு கிடைத்தவுடன் ஒரு வார காலத்திற்குள் வேலை ஆரம்பிக்கப்பட வேண்டும். தவறினால் ஒப்பந்ததாரர் பதிவு ரத்து செய்யப்படும்.
- நிர்வாக காரணங்களுக்காக ஒப்பந்தத்தை எந்த முன் அறிவிப்புமின்றி ஒத்திவைக்கவும், நீக்கிடவும் செயல் அலுவலருக்கு முழு அதிகாரம் உண்டு.
- முடிவு அறிக்கை (CR) பட்டியல் வர பெற்றவுடன் பேரூராட்சியின் நிதி நிலைக்கு ஏற்ப அவ்வப்போது தொகை பட்டுவாடா செய்யப்படும்.
- மதிப்பீடு 5.00 லட்சத்திற்கு மேலுள்ள பணிகளை இணையதளத்தில் செயல் அலுவலர், பேரூராட்சி அலுவலகத்தில் நமூனா டவுன்லோடு செய்து பெற்றுக்கொள்ளலாம். அதற்குரிய டெண்டர் நமூனா தொகையினை வங்கி வரைவு பெற்று டெண்டர் நமூனாவில் இணைக்கப்படவேண்டும். (ஒப்பந்தப்புள்ளி விளம்பரம் தேதிப்படி)

பொதுநிதி திட்டம் (General Fund Scheme) 2007-2008

வ. எண்	பணியின் பெயர்	நீளம்/ எண்ணி-க்கை	மதிப்பீடு (இலட்சம்)	டெண்டர் நமூனா	டேவணித் தொகை	பணி முடிக்க வேண்டிய காலம்
1	குப்பங்குழி வடக்குத்தெரு சிமெண்ட்சாலை அமைத்தல்	90m	2.15	1676	2150	45 நாட்கள்
2	சோமசுந்தரம் காலணி சிமெண்ட்சாலை அமைத்தல்	75m	2.80	1676	2800	45 நாட்கள்

செயல் அலுவலர்
பேரூராட்சி அலுவலகம்
காட்டுமன்னார்கோயில்.

நகல்-

- பேரூராட்சியின் பதிவு பெற்ற ஒப்பந்ததாரர்கள்
- திட்ட அலுவலர் அவர்கள், மாவட்ட ஊரக வளர்ச்சி முகமை கடலூர் அவர்களுக்கு தகவலுக்காக பணிந்தனுப்பப்படுகிறது.
- பேரூராட்சிகளின் உதவி இயக்குநர், கடலூர் அவர்களுக்கு தகவலுக்காக பணிந்தனுப்பப்படுகிறது.
- உதவி செயற்பொறியாளர், பேரூராட்சி பணிகள் உதவி இயக்குநர் அலுவலகம், கடலூர் அவர்களுக்கு தகவலுக்காக அனுப்பப்படுகிறது.
- இளநிலை பொறியாளர், பேரூராட்சி அலுவலகம், அண்ணாமலைநகர் அவர்களுக்கு தகவலுக்காக
- சட்டமன்ற தொகுதி உறுப்பினர் அவர்கள், காட்டுமன்னார்கோயில் சட்டமன்ற தொகுதி, காட்டுமன்னார்கோயில்
- தலைவர், துணைத்தலைவர் மற்றும் உறுப்பினர்கள் பேரூராட்சி , காட்டுமன்னார்கோயில் தகவலறிய
- காட்டுமன்னார்கோயில் பேரூராட்சி எல்லைக்குட்பட்ட அலுவலகங்கள்
- காட்டுமன்னார்கோயில் பேரூராட்சி அலுவலக தகவல் பலகைக்கு

SCHEDULE - A

NAME OF WORK: PROVIDING CEMENT CONCRETE PAVEMENT @ KUPANGUZH NORTH STREET IN KATTUMANNARKOIL TOWN PANCHAYAT

NAME OF TOWN PANCHAYAT : KATTUMANNARKOIL

DATE OF TENDER :

ESTIMATE COST : 2,15,000/-

SOLD TO :

Item No. 1	Probable Quantity 2.	Description of Work 3.	SSRB/M OST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	22.00 Cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stoney each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus earch as shown by the departmental officers at site as per standard specifications.				
2.	33.00 cum	Sand filling with good rivers sand including all labour charges etc. completed				
3	162.00sq m.	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including conveyance of all materials to work site and other incidental charges etc., complete.				

4	17.00 cum	Cement concrete 1:3:6 (One cement three sand and Six hard broken stone) using 20mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of Materials at site and labour charges complete complying with standard specifications.				
5.	33.00 cum	Cement concrete 1:4:8 (One cement four sand and Eight hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.				
6	31.50 Cum	Cement concrete 1:2:4 (One cement Two sand and Four hard broken) Using 20mm ISS gauge hard broken granite stone jelly for foundation including watering wherever necessary and in layers not more than 15 cm in thick etc., including compacting and fixing the expansion joint of bitumen pad and all materials to site and all labour charges and all other including charges etc., completed.				
7	7.00 Sqm	Providing and fixing Bitumen expansion pad including cost and convince of Bitumen Pad and fixing in proper position etc., completed as per standard specification as directed by Engineer. Incharge.				

Signature of Contractor

No. of corrections :
No.of overwritings:

Junior Engineer
Town Panchayat
Annamalainagar

Assistant Executive Engineer
Town Panchayat Works
Cuddalore.

SCHEDULE - A

NAME OF WORK: PROVIDING CEMENT CONCRETE PAVEMENT @ SOMASUNDARAM COLONY IN KATTUMANNARKOIL TOWN PANCHAYAT

Name of town panchayat : Kattumannarkoil

DATE OF TENDER :

ESTIMATE COST : 2, 80,000/-

SOLD TO :

Item No. 1	Probable Quantity 2.	Description of Work 3.	SSRB/M OST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	16.00 Cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stoney each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus earch as shown by the departmental officers at site as per standard specifications.				
2.	50.00 cum	Sand filling with good rivers sand including all labour charges etc. completed				
3	122.00sq m	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including conveyance of all materials to work site and other incidental charges etc., complete.				

4	12.00 cum	Cement concrete 1:3:6 (One cement three sand and Six hard broken stone) using 20mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of Materials at site and labour charges complete complying with standard specifications.				
5.	50.00 cum	Cement concrete 1:4:8 (One cement four sand and Eight hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.				
6	49.00 Cum	Cement concrete 1:2:4 (One cement Two sand and Four hard broken) Using 20mm ISS gauge hard broken granite stone jelly for foundation including watering wherever necessary and in layers not more than 15 cm in thick etc., including compacting and fixing the expansion joint of bitumen pad and all materials to site and all labour charges and all other including charges etc., completed.				
7	10.00 Sqm	Providing and fixing Bitumen expansion pad including cost and convince of Bitumen Pad and fixing in proper position etc., completed as per standard specification as directed by Engineer. Incharge.				

Signature of Contractor

No. of corrections :
No.of overwritings:

Junior Engineer
Town Panchayat
Annamalainagar

Assistant Executive Engineer
Town Panchayat Works
Cuddalore.