

ந.க.எண்: அ1 / 292 / 2007

பேரூராட்சி அலுவலகம்
ஸ்ரீமுஷ்ணம்
நாள்:21.11.2007

கடலார் மாவட்டம்
ஸ்ரீமுஷ்ணம் பேரூராட்சியின் குறுகிய கால ஒப்பந்தப்பள்ளி

1. ஸ்ரீமுஷ்ணம் பேரூராட்சிபகுதியில் அட்டவணையில் குறிப்பிட்டுள்ள வேலைகளை செய்து முடிப்பதற்கான மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகளை இப் பேரூராட்சியில் பதிவு செய்த ஒப்பந்ததாரரிடம் இருந்து பேரூராட்சி செயல் அலுவலர் (அ) அவரது அதிகாரம் பெற்றவரால் 06.12.2007 தேதி வியாழக் கிழமை மாலை 3.00 மணி வரை பேரூராட்சி அலுவலகத்தில் பெற்றுக் கொள்ளப்படும்.
2. ஒப்பந்தப்புள்ளிகளை ஸ்ரீமுஷ்ணம் பேரூராட்சி செயல் அலுவலர் அவர்களின் முகவரிக்கு அனுப்பப்பட வேண்டும். உறையின் மீது எந்த வேலைக்கான ஒப்பந்தப்புள்ளிகள் என்பதை தெளிவாக குறிப்பிட வேண்டும்.
3. அட்டவணையில் குறிப்பிட்டுள்ளபடி வேலைக்குரிய டேவணித்தொகையினை பேரூராட்சி அலுவலகத்தில் ரொக்கமாக செலுத்தி இரசீது பெற்று ஒப்பந்தப்புள்ளியுடன் இணைத்து அனுப்பப்பட வேண்டும்.
4. ஒப்பந்தப்புள்ளி அட்டவணை அடிப்படையில் கோரப்படுகிறது. எனவே, ஒப்பந்தப்புள்ளி நமூனாக்கள் பேரூராட்சி அலுவலகத்தில் 05.12.2007 தேதி புதன் கிழமை முற்பகல் 11.30 மணிவரை வழங்கப்படும். அதற்கான தொகை ஒவ்வொரு பணிக்கும் அதன் எதிரே கண்டுள்ள தொகையினை செலுத்தி பெற்றுக் கொள்ளலாம்.
5. காலம் தவறி வரும் ஒப்பந்தப்புள்ளி மற்றும் முழுமையாகப் பூர்த்தி செய்யப்படாத ஒப்பந்தப்புள்ளிகள் ஒப்பந்த வைப்புத் தொகை செலுத்தாத ஒப்பந்தப்புள்ளிகள் நிராகரிப்படும்.
6. மூடி முத்திரையிடப்படாத ஒப்பந்தப்புள்ளிகள் ஏற்றுக் கொள்ளப்பட மாட்டாது.
7. பணி வரம்பு உள்ளவர்கள் மட்டும் டேவணித் தொகையை செலுத்தி ஒப்பந்தப்புள்ளி கொடுக்க வேண்டும்.
8. பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் ஆஜராகியுள்ள ஒப்பந்ததாரர்கள் முன்னிலையில் 06.12.2007 தேதி வியாழக் கிழமை பிற்பகல் 3.30 மணிக்கு திறக்கப்படும்.
9. அங்கீகரிக்கப்பட்ட ஒப்பந்தப்புள்ளிக்கு ஒப்பந்ததாரர்கள் இலாக்கா சம்மந்தப்பட்ட சட்டதிட்டங்களுக்கு கட்டுப்பட்டு வேலையினை செய்து முடிப்பதற்கான ரூ100/- மதிப்புள்ள முத்திரைத்தாளில் எழுத்து மூலமாக ஒப்பந்தம் செய்து கொடுக்க வேண்டும்.
10. ஒப்பந்தம் செய்யப்பட்ட வேலையினை ஒப்பந்ததாரரே செய்து முடிக்க வேண்டும். கீழ் குத்தகைக்கு விடக்கூடாது.

11. ஓப்பந்ததாரர் செயல் அலுவலர் குறிப்பிடும் இடத்தில் இருந்து இலாக்கா மூலம் வழங்கப்படும் வேலைக்கான பொருட்கள் இருப்பின் பெற்றுக் கொள்ள வேண்டும்.
12. இலாக்கா மூலம் வழங்கப்படும் பொருட்களுக்கு ஓப்பந்த நமுனாவில் குறிப்பிட்டுள்ள உரிய தொகை பிடித்தம் செய்யப்படும்.
13. வேலையினை அதன் எதிரே குறிப்பிட்டுள்ள காலத்திற்குள் செய்து முடிக்க வேண்டும். தவறினால் வைப்புத் தொகையினை பறிமுதல் செய்யப்படுவதுடன் அறிவிப்பு ஏதுமின்றி ஓப்பந்தம் ரத்து செய்யப்படும். அதனால் ஏற்படும் சகல நஷ்டங்களுக்கும் ஓப்பந்ததாரரே பொறுப்பானார்.
14. ஓப்பந்ததாரர் வேலைக்கான உத்திரவு கிடைத்தவுடன் 3 நாட்களுக்குள் வேலையை ஆரம்பிக்கப்பட வேண்டும். தவறினால் ஓப்பந்ததாரர் பதிவு ரத்து செய்யப்படும்.
15. வேலையினை அதன் எதிரே குறிப்பிட்டுள்ள காலகெடுவிற்குள் செய்து முடிக்க வேண்டும். தவறினால் வைப்புத்தொகை பறிமுதல் செய்யப்படுவதுடன் குறிப்பிட்டுள்ள காலத்திற்குள் வேலை செய்து முடிக்க தவறும் பட்சத்தில் மதிப்பீட்டுத் தொகையில் 3 சதவீகிதம் அபராதம் விதிக்கப்படுவதுடன் நாள் 1- க்கு ரூ 500/- அபராதம் விதித்தும் இத்தொகையினை தங்கள் பட்டியலில் பிடித்தம் செய்யப்படும் எனவும், அதற்கான சகல நஷ்டங்களும் ஓப்பந்ததாரரே பொறுப்பாக்கி தொகையினை பட்டியலில் பிடித்தம் செய்யப்படும்.
16. பணியினை அட்டவணையில் குறிப்பிட்ட காலத்திற்குள் முடிக்கப்படாவிடில் கீழ்க்கண்ட விபரப்படி மாவட்ட ஆட்சித் தலைவர் அவர்களின் ந.க.எண்: டிபி1/3407/2003 (2) நாள்: 29.09.2003 ன் படி நடவடிக்கை மேற்கொள்ளப்படும்.
 1. காலக்கெடு முடிந்து முதல் 15 தினங்கள்; வரை 1 சதவீகிதம் ஓப்பந்த விகிதப்படி பட்டியலில் பிடித்தம் செய்யப்படும்.
 2. 15 முதல் 30 தினங்கள் வரை 1 சதவீகிதம் – 2 சதவீகிதம் – 3 சதவீகிதம் ஓப்பந்த விகிதப்படி பட்டியலில் பிடித்தம் செய்யப்படும்.
 3. 30 முதல் 45 வரை 3 சதவீகிதம் – 2 சதவீகிதம் – 5 சதவீகிதம் ஓப்பந்த விகிதப்படி பட்டியலில் பிடித்தம் செய்யப்படும்.
 4. காலக்கெடு முடிந்து 45 நாட்கள் ஆகிவிட்ட நிலையில் தங்களின் ஓப்பந்த டேவணித் தொகை பறிமுதல் செய்வதுடன் ஓப்பந்தப்பதிவு ரத்து செய்யப்படும்.

சட்டமன்ற உறுப்பினர் தொகுதி மேம்பாட்டுத்திட்டம் 2007-2008
(2ம் கைக்கீடு)

வ எண்.	வேலையின் பெயர்	மதிப்பீடு (லட்சத்தில்)	டெண்டர் நழுனா கட்டணம்	டேவணித் தொகை	வேலை செய்துமுடிக்க வேண்டிய காலம்
1	நெசவாளர் காலனியில் மினி பவர் பம்பு அமைத்தல்	1.60	560	4000	2 மாதம்

பாராளுமன்ற உறுப்பினர் தொகுதி மேம்பாட்டுத்திட்டம் 2007-2008

வ எண்.	வேலையின் பெயர்	மதிப்பீடு (லட்சத்தில்)	டெண்டர் நழுனா கட்டணம்	டேவணித் தொகை	வேலை செய்துமுடிக்க வேண்டிய காலம்
1	சேனைத்தலைவர் வீதியில் வடிகால் அமைத்தல்	3.00	560	7500	2 மாதம்

**செயல் அலுவலர்
பேரூராட்சி அலுவலகம்
ஸ்ரீமுஷ்ணம்**

bgWe@:
efšfY:

இப்பேரூராட்சியில் பதிவு செய்யப்பட்ட அனைத்து ஒப்பந்ததாரர்கள்.

திட்ட அலுவலர் மாவட்ட ஊரக வளர்ச்சி முகமை, கடலூர் - 1 அவர்களுக்கு
பணிந்து அனுப்பப்படுகிறது.

” பேரூராட்சிகளின் உதவி இயக்குநர், கடலூர் அவர்களுக்கு தகவலுக்காக
பணிந்து சமர்ப்பிக்கப்படுகிறது.

” உதவி செயற்பொறியாளர் பேரூராட்சிகள் உதவி இயக்குனரகம் கடலூர்
அவர்களுக்கு தகவலறிய அனுப்பி வைக்கப்படுகிறது.

” இளநிலை பொறியாளர், பேரூராட்சி அலுவலகம், அண்ணாமலை நகர்,
தகவலறிய அனுப்பப்படுகிறது.

” தலைவர், துணைத்தலைவர் மற்றும் உறுப்பினர்கள் பேரூராட்சி மன்றம்,
ஸ்ரீமுஷ்ணம் தகவலறிய அனுப்பப்படுகிறது.

” ஸ்ரீமுஷ்ணம் பேரூராட்சி எல்லைக்குட்பட்ட அரசு அலுவலகங்களில்
விளம்பர பலகையில் ஒட்டி விளம்பரம் செய்ய.

” பேரூராட்சி அலுவலக விளம்பர பலகை. ஸ்ரீமுஷ்ணம்

SCHEDULE – A

NAME OF WORK: CONSTRUCTION OF MINI WATER TANK AND
BORE WELL & NESAVALARCOLONY IN SRIMUSHNAM Name of Town panchayat : Srimushnam
TOWN PANCHAYAT

DATE OF TENDER :

ESTIMATE COST : 1,60,000; - **SOLD TO :**

Item No.	Probable Quantity	Description of Work	Unit in Words	Rate In	
				Fig.	Words
1.	1 No	Geophysical survey chargers	Each		
2.	81.00 m	Drilling of borewell in alluvial soil sedimentary strata of clay and sandstone, shale, pebbles boulders etc. by first taking apillot bore of 140/150/200 mm dia and then enlarging to reqd dia by direct or reserve rotary mud circulation method, using contractor's rig, fuel, labour, drilling, betenite mud and water reqd for drilling, at the site shown by the departmental officers including construction of mud pit and transportation (water available with in a lead of 1.50 KM) using clays rig. Drilling of 140/150/200mm pilot bore up to 60 mts. depth ending below G.L.	One Running Meter		
3.	81.00 m	Reaming from 140/150mm dia pilot bore to 300mm dia bore as directed by the departmental officers Upto 60mm	One Running Meter		
4.	1 No	Logging Chargers	Each		
5.	60.00 m 21.00 m 1 No	Labour chargers for inserting PVC casing pipes (with slots or without slots) in drilled hole including jointing the pipes, supplying and packing the annular space with pebbles of size and quality as approved by the departmental officers a) 165mm OD PVC pipes b) 165mm OD PVC slat pipe c) 165mm OD dummy	One Running Meter		
6.	8.00 hrs	Charges for developing the borewell with air compressor of 450 cm capacity (Minimum 8 hours) including transportation labour and fuel charges for compressor as directed by the departmental officers and conducting yield test by "V" Notch method	One Hours		

Item No.	Probable Quantity	Description of Work	Unit in Words	Rate In	
				Fig.	Words
7.	1 No	Materials reqd for the erection of submersible pump supply 2HP motor	Each		
8.	35.00 m	32mm HDPE hose	One Running Meter		
9.	1 No	32mm SS nipple	Each		
10.	40.00 m	2.5 sqm cable	One Running Meter		
11.	1 No	Erection charges of submersible pump set	Each		
12.	1 No	Borewell Top cover	Each		
13.	8.50 m ³	Earth work excavation all classes of soil including with in initial lead and lift as per SS20B etc complete	One cubic metre		
14.	5.50m ³	Sand filling with dry good river sand including cost & conveyance of sand from quarry to site and all labour charges for filling etc complete	One cubic metre		
15.	4.00m ³	Cement concrete 1:4:8 mix using 40mm ISS, HBG metal including cost & conveyance of materials to site and all labour charges for mixing etc complete	One cubic metre		
16.	0.60 m ³	PCC 1:2:4 mix using 20mm ISS HBG metal including cost and conveyance of all materials to site and all labour charges etc complete	One cubic metre		
17.	7.20 m ³	Brick work in cement mortar 1:5 mix using country bricks including cost & conveyance of materials to site and all labour charges etc complete	One cubic metre		
18.	36.50 Kg	Supply and fabrication of steel	One KG		
19.	0.42m ³	RCC 1:2:4 mix using precast slab	One cubic metre		
20.	40.50 m ²	Dadoing with Glazed Tiled with Pointing Cm 1:2 mix including all charges etc complete	One square metre		
21.	42.17 m ²	Plastering with cement mortar 1:4, 12 mm thick including cost & conveyance of all materials to site and all labour charges etc complete	One square metre		

Item No.	Probable Quantity	Description of Work	Unit in Words	Rate In	
				Fig.	Words
22.	25.51 m ²	White washing to coats including all labour charges etc completed	One square metre		
23.	25.51m ²	Colour washing to coats including all labour charges etc completed	One square metre		
24.	1 No	Earth pipe	Each		
25.		Material required			
	5.00 m	a) 32mm G.I pipe	One Running Meter		
	6 Nos	b) 32mm GI Elbow	Each		
	2 Nos	c) 32mm GI nipple	Each		
	1 No	d) 32mm GI union	Each		
	1 No	e) 32mm clampset	Each		
	1 No	f) 2HP panel board	Each		
	1 No	g)service pipe	Each		
	30.00 m	h) 7/20 wire	One Running Meter		
	4 Nos	i) nickel Tap	Each		

Signature of the contractor

No. of corrections:
No.of overwritings:

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

Junior Engineer
Town Panchayat Work
Annamalainagar

SCHEDULE - A

NAME OF WORK : SENAITHALAIVAR STREET

NAME OF TOWN PANCHAYAT : SRIMUSHNAM

DATE OF TENDER :

ESTIMATE COST : 3,00,000

SOLD TO :

Probable Quantity 2.	Description of Work 3.	SSRB/MOST 4.	Unit in Words 5.	Rate In	
				Figures 6.	Words 7.
182.00m ³	Earthwork excavation and depositing on bank with initial load and lift in all classes of soil as per SS20B etc., complete	SSRB 301-310	One cubic metre		
34.00m ³	Sand filling with day and good given sand including cost and conveyance of all to site and including all labour charges etc., complete	SSRB 303	One cubic metre		
34.00m ³	P.C.C. 1:4:8 mix using 40mm ISS HBG metal including cost and conveyance of all materials to work site and including all labour charges etc., complete		One cubic metre		
360.00m ³	Providing centering charges for concrete sides including centering and all labour charges and including all other incidental charges etc.,	MOST 404	One squ. metre		
53.25m ³	P.C.C. 1:2:4 mix using 20mm ISS HBG metal including cost and conveyance of all materials to work site and including labour charges etc. complete	MOST 502	One cubic metre		

Signature of Contractor

No. of corrections :

No. of overwritings:

Assistant Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.