

ந.க.எண். அ1 / 199 / 2008

பேரூராட்சி, புவனகிரி.
நாள் : 12.09.2008.**ஒப்பந்தப்புள்ளி அறிவிப்பு**

புவனகிரி பேரூராட்சியின் 2008-09 ஆம் ஆண்டு அட்டவணையில் குறிப்பிட்ட திட்ட பணியினை மேற்கொள்ள இப்பேரூராட்சியில் பதிவு பெற்ற ஒப்பந்ததாரர்களிடமிருந்து மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகள் 29.09.2008 திங்கள்கிழமை மாலை 3.00 மணி வரை பேரூராட்சி அலுவலகத்தில் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் கீழ்க்காணும் நிபந்தனைக்குட்பட்டு பெற்றுக்கொள்ளப்படும். வரப்பெற்ற ஒப்பந்தப்புள்ளிகள் அன்றைய தினம் 29.09.2008 மாலை 3.30 மணியளவில் ஆஜராகி உள்ள ஒப்பந்ததாரர்கள் முன்னிலையில் திறக்கப்படும். வேலைக்குண்டான ஒப்பந்தப்புள்ளி நமூனா உரிய கட்டணம் செலுத்தி 26.09.2008 வெள்ளிக்கிழமை மாலை 4.00 மணி வரை பேரூராட்சி அலுவலகத்தில் பெற்றுக்கொள்ளலாம்.

வ. எண்	பணியின் விவரம்	நீளம் மற்றும் எண்ணிக்கை	மதிப்பீடு (லட்சத்தில்)	டேவணித் தொகை	ஒப்பந்தப்புள்ளி நமூனா கட்டணம்	பணியினை முடிக்க வேண்டிய காலம்
சட்ட மன்ற உறுப்பினர் உள்ளூர் தொகுதி மேம்பாட்டுத் திட்டம் 2008 - 2009						
1.	சத்துக்குழியில் அங்கன்வாடி கட்டடம் அமைத்தல்	1 நம்	2.00	2000/-	520/-	60-நாட்கள்
2.	முள்ளிப்பள்ளம் ஆதிராவிடர் காலனியில் அங்கன்வாடி கட்டடம் அமைத்தல்	1 நம்	2.00	2000/-	520/-	60-நாட்கள்
3.	பூராசாமிதோப்பு (சௌராஷ்டிரா தெரு) ஈமக்கிரியை மண்டபம் அமைத்தல்	1 நம்	1.75	1750/-	250/-	60-நாட்கள்
4.	தில்லை நகர் தார்சாலை அமைத்தல்	380 மீ	3.00	3000/-	520/-	45-நாட்கள்
5.	ஜி.என்.நகர் தார்சாலை அமைத்தல்	250 மீ	2.00	2000/-	520/-	45-நாட்கள்
6.	இராமசாமி சாலை தார்சாலை அமைத்தல்	250 மீ	2.00	2000/-	520/-	45-நாட்கள்
7.	பேரூராட்சி பகுதியில் மின்சேமிப்பு விளக்குகள் அமைத்தல்	75 நம்	1.50	1500/-	250/-	30-நாட்கள்
பொது நிதி வேலை 2008 - 2009						
8.	புதுத்தெரு வடிகால் அமைத்தல்	32 மீ	0.50	500/-	250/-	45-நாட்கள்
9.	சௌராஷ்டிரா தெரு வடிகால் சீர்செய்தல்	80 மீ	0.55	550/-	250/-	45-நாட்கள்
10.	பாளையக்காரத்தெரு பக்க கால்வாய் அமைத்தல்	60 மீ	1.00	1000/-	250/-	45-நாட்கள்
11.	செட்டிக்குளம் காலனி மெட்டல் சாலை அமைத்தல்	130 மீ	1.20	1200/-	250/-	45-நாட்கள்
12.	ஆதிவராகநத்தம் ஆண்கள் நடுநிலைப்பள்ளி செல்லும் சாலை சிமெண்ட் சாலை அமைத்தல்	60 மீ	1.00	1000/-	250/-	45-நாட்கள்

நிபந்தனைகள்

1. ஒப்பந்தப்புள்ளியில் கலந்துக்கொள்ளும் ஒப்பந்ததாரர்கள், இப்பேரூராட்சியில் திட்ட பணிகள் எடுக்கப்பட்டு பணி உத்தரவில் குறிப்பிட்ட காலகெடுவிற்குள் பணி முடிக்கப்படாமல் இருப்பின் ஒப்பந்தப்புள்ளி நமூனா வழங்கப்படமாட்டாது.
2. ஒப்பந்தப்புள்ளிகள் குறிப்பிட்ட காலக்கெடுவுக்குள் உரிய ஒப்பந்தப்புள்ளி படிவத்தில் பூர்த்தி செய்து கொடுக்கப்பட வேண்டும். காப்புத்தொகை செலுத்தாத ஒப்பந்தப்புள்ளிகளும் காலங்கடந்து வரும் ஒப்பந்தப்புள்ளிகளும் பரிசீலனைக்கு எடுத்துக்கொள்ளப்படமாட்டாது.
3. ஒப்பந்ததாரர் வேலை செய்ய ஆணை வழங்கப்பட்ட உடன் பணி ஆரம்பிக்கும் முன்னர் ரூபாய் 20/- மதிப்புள்ள முத்திரைத்தாளில் ஒப்பந்த உடன் படிக்கை எழுதிக்கொடுக்க வேண்டும்.
4. பணியினை ஆரம்பிக்கும் முன்னர் பொறியியல் அலுவலர்களின் ஆலோசனை பெற்று அதன்படி பணியினை செய்ய வேண்டும்.
5. பட்டியல் வரப்பட்டவுடன் ஒப்பந்தக்காரர்களுக்கு விதிகளின்படி தொகை பட்டுவாடா செய்யப்படும்.
6. மதிப்பீட்டு தொகைக்கு சொத்து மதிப்பு உள்ளவர்கள் மட்டுமே டேவணித்தொகையை செலுத்தி ஒப்பந்தப்புள்ளிகள் கொடுக்க வேண்டும்.
7. ஒப்பந்தப்புள்ளியில் கலந்துக்கொள்ளும் ஒப்பந்ததாரர்கள் 2008-09 ஆம் ஆண்டு செய்தி மக்கள் தொடர்பு அலுவலர் அலுவலகத்தில் ரூ.600/- க்கு ஆண்டு சந்தா தொகை செலுத்திய இரசீது நகல் இணைத்து தரப்படவேண்டும்.
8. ஒப்பந்தப்புள்ளியில் கலந்துக்கொள்ளும் ஒப்பந்ததாரர் 2008-09 ஆம் ஆண்டு ஒப்பந்த பதிவினை புதுப்பித்து இருத்தல் வேண்டும்.
9. ஒப்பந்தப்புள்ளியில் கலந்துக்கொள்ளும் ஒப்பந்ததாரர்கள் 2008-09 ஆம் ஆண்டிற்கு தொழில்வரி பேரூராட்சி அலுவலகத்தில் செலுத்திய இரசீது நகல் இணைத்து தரப்படல்வேண்டும்.
10. பணி துவங்கும் முன்னர் உள்ள நிலையிலும், பணி நடைபெறும் நிலையிலும், பணி முடிக்கப்பட்ட பின்னரும் எடுக்கப்பட்ட புகைப்படங்கள் கொடுக்கப்படவேண்டும்.
11. செயல் அலுவலரால் அவ்வப்போது பிறப்பிக்கப்படும் இதர நிபந்தனைகள்.

செயல் அலுவலர்
புவனகிரி பேரூராட்சி.

பெறுதல் அனைத்து பதிவுப்பெற்ற ஒப்பந்ததாரர்கள் , பேரூராட்சி, புவனகிரி.

நகல் அலுவலக விளம்பரப்பலகை

நகல் தலைவர், உபத்தலைவர், உறுப்பினர்கள், புவனகிரி பேரூராட்சி.

நகல் திட்ட அலுவலர், மாவட்ட ஊரக வளர்ச்சி முகமை, கடலூர் அவர்களுக்கு தகவலுக்காக பணிநிதனுப்பப்படுகிறது.

நகல் உதவி இயக்குநர், பேரூராட்சிகள் கடலூர் மண்டலம், கடலூர் அவர்களுக்கு தகவலுக்காக பணிநிதனுப்பப்படுகிறது.

நகல் உதவி செயற்பொறியாளர், பேரூராட்சி பணிகள், உதவி இயக்குநர் அலுவலகம், கடலூர் அவர்களுக்கு தகவலுக்காக பணிநிதனுப்பப்படுகிறது.

நகல் இளநிலை பொறியாளர், பேரூராட்சி பணிகள், அண்ணாமலைநகர் தகவலுக்காக.

நகல் செயல் அலுவலர், அண்ணாமலைநகர், வடலூர், சேத்தியாதோப்பு, காட்டுமன்னார்குடி, கிள்ளை, லால்பேட்டை பேரூராட்சிகள் தகவலுக்காக.

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE****NAME OF WORK :** CONSTRUCTIONS OF N.M.C. BUILDING @ SUTHUKUZH I IN IN BHUVANAGIRI TOWN PANCHAYAT**ISSUED TO :****EMD :** 2,00,000/-

Executive Officer

DATE OF TENDER : 29.09.2008

Town Panchayat

CHALLAN NO :

Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	30.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	20.00 Cum	Filling in foundation and basement with clear river sand including cost and conveyance of all materials and labour charge for filling and all other incidental charges etc. complete.		One cubic metre		
3.	7.00 Cum	Cement concrete 1:4:8 mix using 40mm ISS HBG metal including cost and conveyance of all materials to site and all labour charges for mixing laying curing the concrete with water and all other incidentals charges etc complete as per standard specification.		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
4.	21.35 Cum	Brick work in cm 1:5 using country bricks of size 8 ¾” x 4 ¼ “ x 2 ¾ “ including cost and conveyance of all materials to site and all labour charges and all other incidental charges etc., completed as per standard specification 10 m3		One cubic metre		
5.	63.20 Sqm	Supply and erecting of centering and shutting including cost and conveyance of all materials to site and all labour charges etc. complete.		One squire metre		
6.	12.00 Qtl	Supplying and fabrication of steel foer all reinforced cement concrete work and placing in position directed by the departmental officers including cost of steel and binding wires and all labour charges etc. complete (Upto 16mm dia)		One Qtl		
7.	19.10 Cum	PCC 1:2:4 mix using 20 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc. completion for foundation and basement.		One cubic metre		
8.	31.00 Sqm	Providing Granolithick floor finish with CC 1:2:4 using 10-12 mm HBG Jelly 25mm thickness 10m3		One squire metre		
9.	255.00 Sqm	Plastering with cement mortor 1:4-12 mm thick including cost and conveyance of all materials to worksite and all labour charges etc., complete.		One squire metre		
10.	50.00 Sqm	Ceiling plastering with cement mortor 1:3-10 mm thick including cost and conveyance of all materials to work site and all labour charges etc., complete.		One squire metre		
11.	2.60 Sqm	Weathering course cement with Brick jelly of 20mm size with pure slacked lime.		One squire metre		
12.	34.50 Sqm	Terrace flooring with pressed tiles in CM1:3 mix using pointing with including cost and conveyance etc., complete.		One squire metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
13.	10.00 Sqm	Supplying and fixing of Cadapah slab 40 thick for cub board slab including of cost and conveyance etc., complete.		One square metre		
14.	1.00 No	Cost and supply of steel doors and windows including of all charges etc., complete.		Each		
15.	15.30 Sqm	Painting of new Iron works with two coats of syntnetic enamel paint of approved colour & Quality over one coat of red oxide for new iron works including cost of all painting materials etc., complete.		One square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : CONSTRUCTIONS OF N.M.C. BUILDING @ MULLIPALLAM AD HABITATION IN BHUVANAGIRI TOWN PANCHAYAT

ISSUED TO :
 EMD : 2,00,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	30.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	20.00 Cum	Filling in foundation and basement with clear river sand including cost and conveyance of all materials and labour charge for filling and all other incidental charges etc. complete.		One cubic metre		
3.	7.00 Cum	Cement concrete 1:4:8 mix using 40mm ISS HBG metal including cost and conveyance of all materials to site and all labour charges for mixing laying curing the concrete with water and all other incidentals charges etc complete as per standard specification.		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
4.	21.35 Cum	Brick work in cm 1:5 using country bricks of size 8 ¾" x 4 ¼ " x 2 ¾ " including cost and conveyance of all materials to site and all labour charges and all other incidental charges etc., completed as per standard specification 10 m3		One cubic metre		
5.	63.20 Sqm	Supply and erecting of centering and shutting including cost and conveyance of all materials to site and all labour charges etc. complete.		One squire metre		
6.	12.00 Qtl	Suppying and fabrication of steel foer all reinforced cement concrete work and placing in position directed by the departmental officers including cost of steel and binding wires and all labour charges etc. complete (Upto 16mm dia)		Qtl		
7.	19.10 Cum	PCC 1:2:4 mix using 20 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc. completion for foundation and basement.		One cubic metre		
8.	31.00 Sqm	Providing Granolithick floor finish with CC 1:2:4 using 10-12 mm HBG Jelly 25mm thickness 10m3		One squire metre		
9.	255.00 Sqm	Plastering with cement mortar 1:4-12 mm thick including cost and conveyance of all materials to worksite and all labour charges etc., complete.		One squire metre		
10.	50.00 Sqm	Ceiling plastering with cement mortar 1:3-10 mm thick including cost and conveyance of all materials to work site and all labour charges etc., complete.		One squire metre		
11.	2.60 Sqm	Weathering course cement with Brick jelly of 20mm size with pure slacked lime.		One squire metre		
12.	34.50 Sqm	Terrace flooring with pressed tiles in CM1:3 mix using pointing with including cost and conveyance etc., complete.		One squire metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
13.	10.00 Sqm	Supplying and fixing of Cadapah slab 40 thick for cub board slab including of cost and conveyance etc., complete.		One squire metre		
14.	1.00 No	Cost and supply of steel doors and windows including of all charges etc., complete.		Each		
15.	15.30 Sqm	Painting of new Iron works with two coats of syntnetic enamel paint of approved colour & Quality over one coat of red oxide for new iron works including cost of all painting materials etc., complete.		One squire metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : CONSTRUCTIONS OF FUNERAL SHED @ BOORASAMY THOPPU (SOWRASHTRA STREET) IN BHUVANAGIRI TOWN PANCHAYAT

ISSUED TO :
 EMD : 1,75,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	67.60 Cum	Earthwork excavation and depositing on bank with initial lead & left SS20B for column foundation.		One cubic metre		
2.	130.50 Cum	Sand Filling with dry river and including cost and all labour charges etc completed.		One cubic metre		
3.	1889.35 Cum	Cement concrete 1:4:8 mix using 40 mm ISS HBG metal including cost and conveyance to site and all charges etc., completed.		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
4.	1872.55 Cum	Bricks work in Cement mortar 1:5 mixing with county Bricks including cost and conveyance to rite and all labour charges and all other mudental charges etc completed.		One cubic metre		
5.	3109.05 Cum	RCC 1:2 :4 mixing 20mm ISS HBG metal including cost and conveyance to site of all materials to work site and all labour charges etc., completed		One cubic metre		
6.	122.50 Sqm	Towards Centering and Shuttering for all RCC items including cost of centering and all labors charges etc completed.		One squire metre		
7.	7.00 Qtl	Supply and fabrication of Steel including cutting bending tying fixing in proper position etc., Completed.		Qtl		
8.	200.00 Sqm	Plastering with cm 1:4-12mm thick including cost and all labour charges etc. completed.		One squire metre		
9.	104.70 Sqm	Plastering with cm 1:3-10 mm thick including cost and all labour charges etc completed.		One squire metre		
10.	305.00 Sqm	Snowcem two coats over the exposed surface of all plastered area etc.		One squire metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Execerutive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : PROVIDING PREMIX CARPET WITH SEALCOAT AT THILLAI NAGAR IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :
 EMD : 3,00,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	24.00 m ³	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc., complete as per standard specification.		One cubic metre		
2.	1140.00 m ²	Picking the existing worn out BT surface including sectioning and replace the metal to camber with power roller rolling etc completed as per standard specification.		One squire metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
3.	86.00 m ³	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification		One cubic metre		
4.	1140.00 Sqm	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One squire metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
5.	1140.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction)		One square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : PROVIDING PREMIX CARPET WITH SEALCOAT AT N.G.NAGAR IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :
 EMD : 2,00,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	28.80 m ³	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc., complete as per standard specification.		One cubic metre		
2.	750.00 m ²	Picking the existing worn out BT surface including sectioning and replace the metal to camber with power roller rolling etc completed as per standard specification.		One squire metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
3.	56.25 m ³	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification		One cubic metre		
4.	750.00 Sqm	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One square metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
5.	750.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction)		One square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : PROVIDING PREMIX CARPET WITH SEALCOAT AT RAMASAMY STREET IN BHUVANAGIRI TOWN PANCHAYAT

ISSUED TO :
 EMD : 2,00,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	27.00 m ³	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murram, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc., complete as per standard specification.		One cubic metre		
2.	750.00 m ²	Picking the existing worn out BT surface including sectioning and replace the metal to camber with power roller rolling etc completed as per standard specification.		One squire metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
3.	56.25 m ³	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification		One cubic metre		
4.	750.00 Sqm	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. Inclusive of cost of bitumen to worksite handling charges for the same at both ends including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One square metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
5.	750.00 Sqm	Providing and laying premix carpet with seal coat type A for 20 mm consolidated thickness using machine crusher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic meter of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.70 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. For seal coat including cost and conveyance of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction)		One square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT

TENDER SCHEDULE

NAME OF WORK : PROVIDING 32 W CFL LIGHT @ BHUVANAGIRI TOWN PANCHAYAT AREA IN BHUVANAGIRI TOWN PANCHAYAT

ISSUED TO :
EMD : 1,50,000/- Executive Officer
DATE OF TENDER : 29.09.2008 Town Panchayat
CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	75.00 Nos	Providing 32 W CFL light including clamp with f other accessories and labour charges for fixing in proper position etc completed.		Each		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : CONSTRUCTION OF DRAIN @ PUTHU THERU (WARD-2) IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :
 EMD : 50,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	23.05 Cum	Earth work excavation and deposition an bank within initial lead and lift as per SS 20 B for lining wall		One cubic metre		
2.	2.60 Cum	Sand filling with good river sand from approved quarry including cost and conveyance of materials and all labour charges etc for leveling course		One cubic metre		
3.	2.60 Cum	PCC 1:4:8 mix using 40 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc.		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
4.	1.30 Cum	PCC 1:2:4 mix using 20 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc.		One cubic metre		
5.	96.00 Sqm	Centering and strutting charges for body wall including cost of centering and all labour charges etc., Completed.		One squire metre		
6.	12.75 Cum	PCC 1:3:6 mix using 40 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc.		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT
TENDER SCHEDULE

NAME OF WORK : CONSTRUCTION OF DRAIN @ SOWRASTRA STREET (WARD-5) IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :

EMD : 55,000/-

DATE OF TENDER : 29.09.2008

CHALLAN NO :

Executive Officer

Town Panchayat

Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	128.60 Sqm	Dismantling the existing damaged plastering surface including removing the dismantling materials and are labour charges etc., completed.		One squire metre		
2.	96.00 Sqm	Towards strutting charges for body wall including cost and centering of all labour charges etc., completed.		One squire metre		
3.	11.05 Cum	PCC 1:2:4 mix using 20 mm ISS HBG metal including cost and conveyance to site of all materials to work site and all labour charges for laying censes including cutting etc., completed.		One cubic metre		
4.	176.00 Sqm	Plastering with CM 1:4-12 mm thick including cost and conveyance to site of all materials to work site and all labour charges etc., completed.		One squire metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : CONSTRUCTION OF DRAIN @ PALAYAKARA STREET (WARD-7) IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :
 EMD : 1,00,000/- Executive Officer
 DATE OF TENDER : 29.09.2008 Town Panchayat
 CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	48.60 Cum	Earth work excavation and deposition an bank within initial lead and lift as per SS 20 B for lining wall		One cubic metre		
2.	5.40 Cum	Sand filling with good river sand from approved quarry including cost and conveyance of materials and all labour charges etc for leveling course		One cubic metre		
3.	5.40 Cum	PCC 1:4:8 mix using 40 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc.		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
4.	2.70 Cum	PCC 1:2:4 mix using 20 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc.		One cubic metre		
5.	180.00 Sqm	Centering and strutting charges for body wall including cost of centering and all labour charges etc., Completed.		One squire metre		
6.	23.85 Cum	PCC 1:3:6 mix using 40 mm ISS HBG metal for lining wall cost and conveyance of materials and all labour charges etc.		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : METALLING CHETTIKULAM AD COLONY STREET IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :

EMD : 1,20,000/-

DATE OF TENDER : 29.09.2008

CHALLAN NO :

Executive Officer

Town Panchayat

Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	59.00 Cum	Earth work excavation in all classes of soils such as hard stifty clay, stiff black cotton, hard red earth, shale's, murrum, ordinary earth, earth mixed with 50 % air-sized boulders etc., with initial leads and lift including laying spreading leveling, sectioning, breading clods etc., as per SS 20A and all other incidental charges etc.,		One cubic metre		
2.	78.00 Cum	Providing and laying U.S. gravel to specified including cost and conveyance of U.S gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick and all other incidental charges etc., completed		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
3.	37.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –II using 1.00 cum of (63 mm to 45mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete		One cubic metre		
4.	37.00 Cum	Providing and laying thickness of water Bound Macadam conforming to Grade –III using 1.00 cum of (53 mm to 22.40mm) IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I value of less than 6 for blind age for 10 sqm of 75 mm Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement labour charges for spreading the metal hand packing to camber edge bunds, slurring, consolidating using power roller, hire, fuel and running charges and all other incidental charges etc. complete as per standard specification		One cubic metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone

BHUVANAGIRI TOWN PANCHAYAT**TENDER SCHEDULE**

NAME OF WORK : PROVIDING CEMENT CONCRETE PAVEMENT @ ADHIVARAGANATHAM MIDDIL SCHOOL STREET
(WARD –15) IN BHUVANAGIRI TOWN PANCHAYAT.

ISSUED TO :
EMD : 1,00,000/- Executive Officer
DATE OF TENDER : 29.09.2008 Town Panchayat
CHALLAN NO : Bhuvanagiri.

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	11.00 Cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stoney each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus earch as shown by the departmental officers at site as per standard specifications.		One cubic metre		

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
2.	81.00 Sqm.	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including conveyance of all materials to work site and other incidental charges etc., complete.		One square metre		
3.	14.15 Cum	Cement concrete 1:5:10 (One cement five sand and ten hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.		One cubic metre		
4.	21.80 Cum	Cement concrete 1:2:4 (One cement Two sand and Four hard broken) Using 20mm ISS gauge hard broken granite stone jelly for foundation including watering wherever necessary and in layers not more than 15 cm in thick etc., including compacting and fixing the expansion joint of bitumen pad and all materials to site and all labour charges and all other including charges etc., completed.		One cubic metre		
5.	3.38 Sqm	Providing and fixing Bitumen expansion pad including cost and convince of Bitumen Pad and fixing in proper position etc., completed as per standard specification as directed by Engineer. Incharge.		One square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Junior Engineer
Town Panchayat Works
Annamalai Nagar.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone