

SCHEDULE - A

NAME OF WORK : **PROVIDING B.T ROAD AT VOC NAGAR IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **3,87,656/-**

ESTIMATE COST : **4,00,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	53.00 ³	Earth work excavation in all classes of soils such as hard stiff clay, stiff black cotton, hard red earth, shales, murrum, ordinary earth, earth mixed with 50% fairsized boulders etc., with initial leads and lift including laying, spreading, leveling, sectioning, breaking clods etc., as per SS 20 A and all other incidental charges etc., complete as per standard specification.	SSRB 301-310	One cubic metre		
2.	379.00m ³	Providing and laying U.S. gravel to the specified thick including cost and conveyance of U.S. gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick (or) as specified by the departmental officer, leveling, sectioning etc. and all other charges for tools and plants employed for the work and all other incidental charges such as barricading and providing danger lights etc; complete as per standard specification	SSRB 303	One cubic meter		
3	82.00 m ³	Providing and laying 75mm consolidated thickness of water bound macadam conforming to Grade II using 1.00 cum of 90.00 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I. value of less than 6 for blindage for 10 sqm. Of 75 mm. complete as per standard specification.		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	82.00 m ³	<p>Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade – III using 1.00 cum. Of 63 mm to 11.20 mm IRC size dragged hard broken granite metal with 0.24 cum of gravel which shall have a P.I. Value of less than 6 for blindage for 10 sqm. of 75 mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement, labour charges for spreading the metal, hand packing to camber, blinding with gravel, watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction, hire, fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights etc., complete as per standard specification, for Top layer (payment shall be made for finished item of work after compaction).</p>	MOST 404	One cubic metre		
5.	1088.00 m ²	<p>Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. inclusive of cost bitumen including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.</p>	MOST 502	One Square metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

6.	1088.00 m ²	Providing and laying premix carpet with seal coat type A for 20mm consolidated thickness using machine cursher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic metre of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.75 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. for seal coat including cost and conveyance of of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller rolling etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).	MOST 509-513	One Square metre		
----	---------------------------	---	-----------------	------------------	--	--

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : **PROVIDING DRAINAGE AT ANGALAMMAN KOIL STREET IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **3,20,155/-**

ESTIMATE COST : **3,30,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	208.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, stiff black cotton, hard red earth, shales, murrum, ordinary earth, earth mixed with 50% fairsized boulders etc., with initial leads and lift including laying, spreading, leveling, sectioning, breaking clods etc., as per SS 20 B and all other incidental charges etc., complete as per standard specification		One cubic metre		
2.	37.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic meter		
3	25.00 M ³	Cement concrete 1:5:10 (one cement five sand and ten H.B.B.G metal) using 40mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per specification.		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	697.00 M ²	Shuttering using Rough face form work the charges Inclusive of all labour, material, nails, proper soffit including all charges etc. complete.		One Square metre		
5.	81.00 M ³	Cement concrete 1:3:6 (one cement Three sand and six H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing, laying and consolidation including cost of curing etc, complete as per standard specification		One cubic metre		
6.	2.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing, laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
7.	120.00 Kg	Supply and fixing of steel reinforcements as per drawing. The charges inclusive of cutting, bending, nails all material, labour etc complete as per standard specification.		One Kilo gram		
8.	125.00 M ³	Removal of surplus earth from site to 1km. The charges inclusive of all labour, material, Engaging using tipper Tractor etc complete as per standard specification.		One cubic metre		
9.	125.00 M ²	Plastering in C.M1:4-12mm thick using fine course of sand including all material, labour etc complete as per standard specification.		One Square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : **PROVIDING BUS SHELDER AT SORNAVUR TO NATHAMEDU SALAI IN MELPATTAMPAKKAM TOWN PANCHAYAT**
VALUE OF CONTRACT : **92,867/-**
ESTIMATE COST : **1,00,000/-**

NAME OF TP : Melpattampakkam
DATE OF TENDER : 16-11-2007
SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	7.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	4.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		
3	4.00 M ³	Random Rubble masonry in C.M.1:5 mix using new rough and bond stones including cost & conveyance of all materials etc., complete including cost of cement which will be supplied by departmental of deptl. Stone and conveyance to site at his own cost including and labour charges and all other incidental charges etc.. complete as per standard specifications.		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	1.00 M ³	Brick work in cement mortar 1:5 using 1st class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
5.	49.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete.		One Square metre		
6.	500.00 Kg	Supplying and Fabrication of steel including cost and conveyance of all materials to site and all labour charges etc., complete		One Kilo gram		
7.	5.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
8.	37.00 M ²	Finishing the top of Roof machine pressed tiles of size 23x23x2 cm Thicks and including cost and conveyance of all labour charges etc.,		One Square metre		10,710.00

Signature of Contractor :

No. of Corrections :

No. of over writings :

9.	34.00 M ²	Floor Finishing with ceramic tiles including cost and conveyance of all labour charges etc.,		One Square metre		17,340.00
10.	100.00 Kg	Supplying and fixing of grill work including cost and conveyance of all labour charges etc., complete complying with standard specification		One Kilo gram		4200.00
11.	49.00 M ²	Plastering with c.m 1:3-10mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		2891.00
12	49.00 M ²	Colour washing two coats using with approved colour Pigments including cost and conveyance of all charges etc., complete		One Square metre		428.00

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : CONSTRUCTION OF DINNING HALL AT COMMUNITY CENTRE IN MELPATTAMPAKKAM TOWN PANCHAYAT

VALUE OF CONTRACT : 4,18,375/-

ESTIMATE COST : 4,50,000/-

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	37.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	53.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic meter		
3	18.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	24.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
5.	190.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete.		One Square metre		
6.	3600.00 Kg	Supplying and Fabrication of steel including cost and conveyance of all materials to site and all labour charges etc., complete		One Kilo gram		
7.	32.00 M ³	Brick work in cement motor 1:5 using Ist class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
8.	415.00 M ²	Plastering with c.m 1:5-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
9.	80.00 M ²	Plastering with c.m 1:3-10mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
10.	80.00 M ²	White washing with best shell lime including all cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

11.	415.00 M ²	Colour washing with using best colour pigments cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		
12	24.00 M ²	Painting with new wood surface using enamel paints including all labour charges etc complete as per standard specification.		One Square metre		428.00
13	80.00 M ²	weathering course and one course pressed tiles cost & conveyance to site and all labour charges etc as per standard specification.		One Square metre		
14	D-1 No W-5 Nos	Supply and fixing of doors and windows including all labour charges etc as per standard specification.		No		
15	405.00 sqft	Supply and fixing of cuddapah slab with proper pointing including all labour charges, material etc as per standard specification.		One Square Feet		
16	8 Nos	wiring with light point wiring suitable quality cables and fitting including all cost & conveyance of materials as per standard specification.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

17	6 Nos	wiring with fan point in wiring suitable quality cables and fitting including all cost & conveyance of materials as by standard specification.		No		
18	2 Nos	Wiring with flug point in wiring suitable quality cables and fitting including all cost & conveyance of materials as by standard to site all labour charges.		No		
19	1 No	Supply and fixing of 30 amps DPIC main switch including all cost & conveyance of materials to site all labour charges.		No		
20	1 No	Supply and fixing of 5A in 20 Amps for AC single phase 230V. 50Hz, watt hour meter on suitable T.W bend complete with earth connection.(Main Board)		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : **CONSTRUCTION OF KITCHEN ROOM AT COMMUNITY CENTRE IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **98,777/-**

ESTIMATE COST : **1,00,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	14.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	11.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic meter		
3	3.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	7.00 M ³	Cement Concrete 1:2:4 mix (one cement two and four aggregate) using 20 mm I.R.C.H.B.B.G. metal including cost of forming the form work and laying the concrete inside the form work to proper gradient with required expansion joint etc wherever necessary including consolidation by wooden rammer including of cost curing up to the specified period as per standard specification		One cubic metre		
5.	55.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete.		One Square metre		
6.	650.00 Kg	Supplying and Fabrication of steel including cost and conveyance of all materials to site and all labour charges etc., complete		One Kilo gram		
7.	14.00 M ³	Brick work in cement motor 1:5 using Ist class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
8.	117.00 M ²	Plastering with c.m 1:5-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
9.	14.00 M ²	Plastering with c.m 1:3-10mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
10.	131.00 M ²	Colour washing with using best colour pigments cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

11	8.00 M ²	Painting with new wood surface using enamel paints including all labour charges etc complete as per standard specification.		One Square metre		
12	D-1 No W-1 No	Supply and fixing of doors and windows including all labour charges etc as per standard specification.		No		
13	1No	Supply and fixing of RCC jally of size 0.90 mx0.60 m including all labour charges, material etc complete as per standard specification.		No		
14	2 Nos	wiring with light point wiring suitable quality cables and fitting including all cost & conveyance of materials as by standard specification.		No		
15	1 No	Wiring with plug point in wiring suitable quality cables and fitting including all cost & conveyance of materials as by standard to site all labour charges.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : **CONSTRUCTION OF TOILET BUILDING AT COMMUNITY CENTRE IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **1,80,055/-**

ESTIMATE COST : **2,00,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	45.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation.		One cubic metre		
2.	14.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic meter		
3	8.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	6.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
5.	26.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete.		One Square metre		
6.	900.00 Kg	Supplying and Fabrication of steel including cost and conveyance of all materials to site and all labour charges etc., complete		One Kilo gram		
7.	28.00 M ³	Brick work in cement motor 1:5 using Ist class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
8.	168.00 M ²	Plastering with c.m 1:5-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
9.	20.00 M ²	Plastering with c.m 1:3-10mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
10.	188.00 M ²	Colour washing with using best colour pigments cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

11	19.00 M ²	Painting with new wood surface using enamel paints including all labour charges etc complete as per standard specification.		One Square metre		
12	6 No	Supply and fixing of doors and windows including all labour charges etc as per standard specification.		No		
13	6 No	Supply and fixing of RCC Jally of size 0.90 mx0.60 m including all labour charges etc complete as per standard specification.		No		
14	55.00 M ²	Floor finishing with tiles in 0.34x0.34x6mm including all cost & conveyance to site and all labour charges as per specification		One Square metre		
15	3 Nos	Towards cost & supply of water closet including all cost & conveyance of materials to site and all labour charges.		No		
16	15 Rm	Supply and fixing of 4'' PVC pipe for out side delivery pipe including all cost & conveyance to site and all labour charges as per specification.		One Running metre		
17	20 Rm	Supply and fixing of 1'' PVC pipe for In side including all cost & conveyance to site and all labour charges as per specification.		One Running metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

18	25 Rm	Supply and fixing of 3/4" PVC pipe for In side including all cost & conveyance to site and all labour charges as per specification.		One Running metre		
19	8 Nos	wiring with light point wiring suitable quality cables and fitting including all cost & conveyance of materials as by standard specification.		No		
20	2 Nos	Wiring with flug point in wiring suitable quality cables and fitting including all cost & conveyance of materials as by standard to site all labour charges.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : CONSTRUCTION OF 10000 LITRES CAPACITY OHT AT COMMUNITY CENTRE IN MELPATTAMPAKKAM TOWN PANCHAYAT
 VALUE OF CONTRACT : 1,05,585/-
 ESTIMATE COST : 1,30,000/-

NAME OF TP : Melpattampakkam
 DATE OF TENDER : 16-11-2007
 SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	A) 18.39 M ³ B) 0.36 M ³	Earth work excavation in hard stiff clay, still black cotton, hard red, shells murums gravel, stoney earth and earth mixed with small boulders and hard gravelly soil slope of 1m in 4 and including dewatering charges etc. complete as per standard specification. A) First depth of 2m B) Second depth of 1m		One cubic metre		
2.	1.35 M ³	Supplying and filling of Good quality River sand from approved quarry including all labour charges etc., complete as per standard specification		One cubic meter		
3	0.90 M ³	PCC.1:4:8(one cement, four sand and eight aggregates) using 40mm HBG for leveling course including the cost of mixing concrete, ramming, curing etc., complete as directed by TWAD Board officers.		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	<p>A)1.234 M³ B)0.703 M³ C)1.453 M³ D)3.40 M³ E)1.696 M³</p>	<p>RCC.1:1.5:3 (one cement, one and half sand and three aggregates) using 20mm HBGS excluding cost of reinforcement, centering, shuttering strutting, but including cost of mixing concrete, placing, vibrating with mechanical vibrator, finishing, curing etc., complete as directed by TWAD Board officers.</p> <p>A) For items 1.5m to 4.5m belowGL B) Items 0 to 1.5m below G.L C) Above GL & upto 4.5m D) Above 4.51m & upto 7.32m fromGL E) From 7.33m to 10.98m</p>		One cubic metre		
5.	<p>A)59.506 M² B)42.55 M² C)25.80 M²</p>	<p>Supply and erecting steel centering for sides and soffits including necessary supports and shuttering to the required height for RCC items using MS sheets or suitable size of BG.10 stiffened with welded MS angles of size 25mm x 25mmx3mm of boarding, laid over silver oak joints of size 10cm x 6.5cm spaced at 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre complying with standard specifications etc., completed and as directed by TWAD Board officers.</p> <p>A) Plane surface B) Curved surface C) Square columns</p>		One Square metre		
6.	64.622 M ²	<p>Painting two coats with approved cement paint over one coat of priming coat over cement plastered exposed surface of the Reservoir including cleaning, preparing the surface and curing etc., complete and as directed by TWAD Board officers.</p>		One Square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

7.	759.00 Kg	Supply and Fixing of steel reinforcements as per drawing including all labour charges etc., completed and as directed by TWAD Board officers.		One Kilo grame		
8.	1 No	Fabrication, supply, delivery and fixing of outside MS ladder wide 45cm made out of 50x50x6mm MS angle for sides and steps in 16mm MS pain rods fixed at 30cm centre to centre welded, jointed etc..		No		
9.	1 No	Providing and fixing of RCC inner access ladder in RCC 1:1:5:3 (one cement, one and half sand and three aggregates) using 20mm HBG stone foe OHT including all labavour charges. Etc.,		No		
10.	2 Nos	Providing PVC ventilating arrangements mosquito proof nylon net with 110mm PVC cowl and as directed by TWAD Board officers.		No		
11	1 No	Providing cut stone slab in CM 1:3 and as directed by TWAD Board officers.		No		
12	1 No	Providing manhole cover of size 0.60 x 0.60m in RCC 1:1:5:3 with suitable reinforcement and 50x50 in CM 1:3 and as directed by TWAD Board officers.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

13	1 No	Painting TWAD Board emblem on the SR with enamel paint as per Board's specification and as directed by TWAD Board officers.		No		
14	14.563 M ³	Refilling the foundation with excavated earth including consolidation as directed by the TWAD Board officers.		One cubic metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : DESILTING OF KARAIYAN KUTTAI IN MELPATTAMPAKKAM TOWN PANCHAYAT

VALUE OF CONTRACT : 1,73,283/-

ESTIMATE COST : 1,90,000/-

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	4125.00 M ³	Earth work excavation in hard stiff clay, still black cotton, hard red, shells murums gravel, stoney earth and earth mixed with small boulders and hard gravelly soil slope of 1m in 4 and including dewatering charges etc. complete as per standard specification.		One cubic metre		
2.	2060.00 M ³	Formation of bund and clearing the soil from site to 2 km all material, labour, etc complete as per standard specification.		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : **CONSTRUCTION OF RETAINING WALL AT KARAIYAN KUTTAI IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **2,90,157/-**

ESTIMATE COST : **3,10,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	95.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	14.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic meter		
3	114.00 M ³	Cement concrete 1:3:6 (one cement three sand and six metal) mixing using 20mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	150.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete as per standard specification.		One Square metre		
5.	7.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
6.	2.00 M ³	Brick work in cement motor 1:5 using Ist class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
7.	90.00 M ²	Plastering with c.m 1:4-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
8.	75.00 M ²	White washing with best shell lime including all cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : PROVIDING CEMENT CONCRETE PAVEMENT AT S.V.S NAGAR IN MELPATTAMPAKKAM TOWN PANCHAYAT

VALUE OF CONTRACT : 3,36,979/-

ESTIMATE COST : 3,50,000/-

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	28.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20A inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	49.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic meter		
3	62.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4	22.00 M ³	Cement Concrete 1:3:6 mix (one cement two sand and four aggregate) using 20 mm I.R.C.H.B.B.G. metal including cost of forming the form work and laying the concrete inside the form worl to proper gradient with required expansion joint etc wherever necessary including consolidation by wooden rammer including of cost curing up to the specified period as per standard specification.		One cubic metre		
5.	217.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete as per standard specification.		One Square metre		
6.	62.00 M ³	Cement Concrete 1:2:4 mix (one cement two sand and four aggregate) using 20 mm I.R.C.H.B.B.G. metal including cost of forming the form work and laying the concrete inside the form worl to proper gradient with required expansion joint etc wherever necessary including consolidation by wooden rammer including of cost curing up to the specified period as per standard specification.		One cubic metre		
7.	47.00 M ²	Plastering with c.m 1:4-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		

Signature of Contractor :

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : PROVIDING MARK II HAND PUMP AT MELPATTAMPAKKAM SUDUKADU IN MELPATTAMPAKKAM TOWN PANCHAYAT
 VALUE OF CONTRACT : 54,177/-
 ESTIMATE COST : 60,000/-

NAME OF TP : Melpattampakkam
 DATE OF TENDER : 16-11-2007
 SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	1 No	Towards labour charges for conducting geophysical survey. The charges inclusive of all survey equipments, material, labour etc complete as per standard specification		No		
2.	45.00 Rm	Drilling of bore wells of size 300mm in sedimentary formation using hand bore sets including supplying and packing of pebbles and conveyance of hand bore set including loading and unloading etc complete.		One Running meter		
3	45.00 Rm	Cost and supply of 150mm dia PVC casing pipe including cost and conveyance of all materials including hire and fuel for tools and machineries etc., complete.		One Running meter		
4	45.00 Rm	Labour charges for Inserting casing pipe including cost and conveyance of all materials, labour etc complete as per standard specification		One Running meter		

Signature of Contractor :

No. of Corrections :

No. of over writings :

5	1 No	Supply and delivery of India Mark II Hand pump set including cost and conveyance of all materials, labour etc complete as per standard specification.		No		
6	1 No	Labour charges for erection of Mark II Hand pump including cost and conveyance of all materials, labour etc complete as per standard specification.		No		
7	1 No	Construction of plat form to a size of 1.80x1.80 and with PCC 1:2:4 and top finish with cm 1:3, 20mm thick including all labour etc complete as per standard specification.		No		
8	8 Hours	Developing bore well with air compressor including all labour etc complete as per standard specification.		One Hour		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE – A

NAME OF WORK : **CONSTRUCTION OF BURIAL GROUND SHED AT NATHAMEDU IN MELPATTAMPAKKAM TOWN PANCHAYAT**
VALUE OF CONTRACT : **99,682/-**
ESTIMATE COST : **1,00,000/-**

NAME OF TP : Melpattampakkam
DATE OF TENDER : 16-11-2007
SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	20.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	8.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic metre		
3.	2.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4.	600.00 Kg	Supplying and Fabrication of steel including cost and conveyance of all materials to site and all labour charges etc., complete		One Kilo gram		
5.	99.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete.		One Square metre		
6.	14.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
7.	193.00 M ²	Plastering with c.m 1:4-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
8.	193.00 M ²	Colour washing with using best colour pigments cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		
9.	3 Nos	Cost and supply of A.C cowel including all cost and conveyance to site and all Labour charges etc.,.		No		
10.	50.00 M ²	Terrace flooring and roof using pressed tiled including all cost and conveyance to site and all labour charges.		One Square metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : **PROVIDING B.T ROAD AT NATHAMEDU SUDUKADU ROAD IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **2,28,043/-**

ESTIMATE COST : **2,35,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	36.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, stiff black cotton, hard red earth, shales, murrum, ordinary earth, earth mixed with 50% fairsized boulders etc., with initial leads and lift including laying, spreading, leveling, sectioning, breaking clods etc., as per SS 20 A and all other incidental charges etc., complete as per standard specification.		One cubic metre		
2.	750.00 M ²	Picking the existing B.T surface 3 to 5 cm deep removal of picked up stuff to the side berms and using the useful metal to the road hand packing to camber sectioning, leveling, etc., complete as per including labour charges for picking and other tools and plants etc., complete as per standard specification.		One Square metre		
3.	36.00 m ³	Providing and laying U.S. gravel to the specified thick including cost and conveyance of U.S. gravel from approved quarry and stacking the same at road side to departmental gauge for premeasurement as directed by the departmental officers including labour charges for spreading in layers not exceeding 75 mm thick (or) as specified by the departmental officer, leveling, sectioning etc. and all other charges for tools and plants employed for the work and all other incidental charges such as barricading and providing danger lights etc; complete as per standard specification		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4.	57.00 m ³	Providing and laying 75mm consolidated thickness of water bound macadam conforming to Grade II using 1.00 cum of 90.00 mm to 22.40 mm IRC size graded hard broken granite metal with 0.24 cum of gravel which shall have a P.I. value of less than 6 for blindage for 10 sqm. Of 75 mm. complete as per standard specification.		One cubic meter		
5.	57.00 m ³	Providing and laying 75 mm consolidated thickness of water Bound Macadam conforming to Grade – III using 1.00 cum. Of 63 mm to 11.20 mm IRC size dragged hard broken granite metal with 0.24 cum of gravel which shall have a P.I. Value of less than 6 for blindage for 10 sqm. of 75 mm. Consolidated thickness, including cost and conveyance of metal and gravel from the approved quarry to work site and stacking the same at road side to departmental gauge for premeasurement, labour charges for spreading the metal, hand packing to camber, blinding with gravel, watering with all leads for soft water forming edge bunds, slurring, consolidating using power roller to achieve the specified compaction, hire, fuel and running charges for power roller and all other tools and plants employed and all other incidental charges such as barricading, providing danger lights etc., complete as per standard specification, for Top layer (payment shall be made for finished item of work after compaction).		One cubic metre		
6.	750.00 m ²	Providing tack coat over W.B.M. surface using 4 kg of bitumen per 10 sqm. inclusive of cost bitumen including heating the bitumen to the required temperature, labour charges for brushing, cleaning and preparing the surface for laying the tack coat and labour for applying the required quantity of bitumen including hire, fuel and running charges for the bitumen sprayer and pumping arrangements and all other tools and plants is employed for the work including all other incidental charges such as barricading and providing danger lights, flags etc., complete as per standard specification.		One Square metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

7.	750.00 m ²	Providing and laying premix carpet with seal coat type A for 20mm consolidated thickness using machine cursher I.R.C. size HBG metal 0.18 cubic metre of 13.2 mm and 0.09 cubic metre of 11.2 mm with 14.60 kg. of bitumen for premixing for 10 sqm of premix carpet and 0.09 cum of 6.75 mm IRC, HBG crusher metal with 9.80 kg. of bitumen per 10 sqm. for seal coat including cost and conveyance of of all materials from approved quarry to worksite and stacking them to departmental gauge for premeasurement including labour charges for heating the bitumen to the required temperature and mixing the required quantity of metal and bitumen using Mini Hot Mix plant conveying the mix by wheel borrows including labour charges for spreading the mix to grades lines and profile and consolidation with power roller rolling etc., including hire, fuel and running charges for Mini Hot Mix plant and power roller and all other tools and plants employed and all other incidental charges such as barricading and providing danger lights etc., complete complying with standard specification (payment shall be made for finished item of work after compaction).		One Square metre		
----	--------------------------	---	--	------------------	--	--

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : CONSTRUCTION OF BURIAL GROUND SHED AT MELPATTAMPAKKAM SUDUKADU IN MELPATTAMPAKKAM TOWN PANCHAYAT
VALUE OF CONTRACT : 1,98,414/-
ESTIMATE COST : 2,00,000/-

NAME OF TP : Melpattampakkam
DATE OF TENDER : 16-11-2007
SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	31.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	15.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic metre		
3.	11.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4.	1500.00 Kg	Supplying and Fabrication of steel including cost and conveyance of all materials to site and all labour charges etc., complete		One Kilo gram		
5.	166.00 M ²	Centering for soffits of reinforcements including cost and conveyance of all materials to site and all charges etc.. complete.		One Square metre		
6.	23.00 M ³	Cement concrete 1:2:4 (one cement Two sand and Four H.B.B.G metal) using 20mm metal including cost and conveyance of all metal to work site, including cost of mixing. laying and consolidation including cost of curing etc, complete as per standard specification.		One cubic metre		
7.	342.00 M ²	Plastering with c.m 1:4-12mm thick including cost and conveyance of all materials to site and all charges etc., complete		One Square metre		
8.	342.00 M ²	Colour washing with using best colour pigments cost and conveyance to site and all Labour charges etc complete as per standard specification.		One Square metre		
9.	3 Nos	Cost and supply of A.C cowel including all cost and conveyance to site and all Labour charges etc.,.		No		
10.	94.00 M ²	Terrace flooring and roof using pressed tiled including all cost and conveyance to site and all labour charges.		One Square metre		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : **PROVIDING CHILDREN'S PARK AT VENKATA KRISHNA NAGAR IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **2,34,317/-**

ESTIMATE COST : **2,50,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	36.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	21.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic metre		
3.	2.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4.	5.00 M ³	Brick work in cement mortar 1:5 using 1st class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
5.	126.00 M ²	Plastering with c.m 1:5-10mm thick including cost and conveyance of all materials to site and all charges etc., complete as per standard specifications.		One Square metre		
6.	300.00 Kg	Providing and fixing of grill work. The charges inclusive of all labour, material etc complete as per standard specifications.		One Kilo gram		
7.	3 Nos	Towards supply and fixing of slide with ladder. The charges inclusive of all labour, material etc complete as per standard specifications..		No		
8.	4 Nos	Towards supply and fixing of Horizontal ladder The charges inclusive of all labour, material etc complete as per standard specifications.		No		
9.	8 Nos	Towards supply and fixing of fibre FRB moulded chairs. The charges inclusive of all labour, material etc complete as per standard specifications.		No		
10.	5 Nos	Towards supply and fixing of Lamp post with fitting. The charges inclusive of all labour, material etc complete as per standard specifications.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

11.	1 No	Towards providing and laying of ornamental fountain. The charges inclusive of all labour, material etc complete as per standard specifications.		No		
12.	120.00 M ³	Supply and fixing of red earth. including all labour charges, material etc complete.		One cubic metre		
13.	60.00 M ²	Supply and laying of Korean Gress including cost and conveyance of all materials, labour, etc. complete as per standard specifications.		One Square metre		
14.	125 Nos	Providing and laying of ornamental plants. The charges inclusive of all labour, material etc complete as per standard specifications.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

SCHEDULE - A

NAME OF WORK : **PROVIDING CHILDREN'S PARK AT BALAJI NAGAR IN MELPATTAMPAKKAM TOWN PANCHAYAT**

VALUE OF CONTRACT : **2,37,236/-**

ESTIMATE COST : **2,50,000/-**

NAME OF TP : Melpattampakkam

DATE OF TENDER : 16-11-2007

SOLD TO :

Item No. 1.	Probable Quantity 2.	Description of Work 3.	SSRB/ MOST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	36.00 M ³	Earth work excavation in all classes of soils such as hard stiff clay, still black cotton soil, hard red, earth mixed with 50% fair sized boulders and hard gravelly soil and depositing on bank with initialed and lift as per SS 20B inclusive of shoring structing waling and bailing out water where ever necessary forming protective bunds, coffer dams and including refilling charges around and all other incidental charges etc., complete complying with specification for foundation		One cubic metre		
2.	21.00 M ³	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.		One cubic metre		
3.	16.00 M ³	Cement concrete 1:5:10 (one cement five sand and Ten metal) mixing using 40mm ISS size hard blue granite metal from approved quarry including cost and conveyance of all materials site, including cost of cement which will be procured by the contractor at his own cost including conveyance to the site and handling charges for mixing lay in, leveling, compacting with all elands and lift with good soft potable water curing and all other incidental charges such as providing from work if necessary shoring, incidental charges etc., complete complying with standard specification for foundation and flooding		One cubic meter		

Signature of Contractor:

No. of Corrections :

No. of over writings :

4.	21.00 M ³	Random Rubble masonry in C.M.1:5 mix using new rough and bond stones including cost & conveyance of all materials etc., complete including cost of cement which will be supplied by departmental of deptl. Stone and conveyance to site at his own cost including and labour charges and all other incidental charges etc.. complete as per standard specifications.		One cubic metre		
5.	18.00 M ³	Brick work in cement motor 1:5 using Ist class country bricks including cost and conveyance of all material, labour etc. complete as per standard specifications.		One cubic metre		
6.	126.00 M ²	Plastering with c.m 1:5-10mm thick including cost and conveyance of all materials to site and all charges etc., complete as per standard specifications.		One Square metre		
7.	1390.00 Kg	Providing and fixing of grill work. The charges inclusive of all labour, material etc complete as per standard specifications.		One Kilo gram		
8.	1 No	Towards supply and fixing of slide with ladder. The charges inclusive of all labour, material etc complete as per standard specifications..		No		
9.	2 Nos	Towards supply and fixing of Horizontal ladder The charges inclusive of all labour, material etc complete as per standard specifications.		No		
10.	4 Nos	Towards supply and fixing of fibre FRB moulded chairs. The charges inclusive of all labour, material etc complete as per standard specifications.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

11.	2 Nos	Towards supply and fixing of Lamp post with fitting. The charges inclusive of all labour, material etc complete as per standard specifications.		No		
12.	1 No	Towards providing and laying of ornamental fountain. The charges inclusive of all labour, material etc complete as per standard specifications.		No		
13.	62.00 M ³	Supply and fixing of red earth. including all labour charges, material etc complete.		One cubic metre		
14.	47.00 M ²	Supply and laying of Korean Gress including cost and conveyance of all materials, labour, etc. complete as per standard specifications.		One Square metre		
15.	75 Nos	Providing and laying of ornamental plants. The charges inclusive of all labour, material etc complete as per standard specifications.		No		

Signature of Contractor:

No. of Corrections :

No. of over writings :

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.