

மேல்பட்டாம்பாக்கம் பேரூராட்சி.

கடலூர் மாவட்டம்

குறுகிய கால ஒப்பந்தப்புள்ளி கோரும் அறிவிக்கையின் விபரம்

- ஒப்பந்தப்புள்ளி கோரும் அலுவலரின் பெயர் : திரு. மூ. கலைப்பாண்டி,
செயல் அலுவலர்,
மேல்பட்டாம்பாக்கம் பேரூராட்சி.
- அ) திட்டத்தின் பெயர்/கொள்முதல் : 12-வது நிதிக்குழுத் திட்டம் -2007-08
செய்யப்படும் பணிகள்

பணியின் விபரம்

வ. எண்	வேலையின் பெயர்	மதிப்பீடு	டெண்டர் ஷெட்யூல் படிவத் தொகை ரூ	முன் வைப்புத் தொகை ரூ .	பணி முடிக்கப் பட வேண்டிய காலம்
1.	12-வது நிதிக்குழுத் திட்டம்- 2007-08 மேல்பட்டாம்பாக்கம் ஊராட்சி ஒன்றிய துவக்கப்பள்ளி மதில் சுவர் கட்டுதல்.	4,70,000/-	3380-	4700-	30 நாட்கள்

- ஆ). பணி அல்லது கொள்முதல் நடைபெறும் மாவட்டத்தின் பெயர் : கடலூர் மாவட்டம்
- எந்த இடத்தில் எந்த தேதிவரை என்ன விலைக்கு ஒப்பந்தப்புள்ளி சம்பந்தமாக படிவம் கிடைக்கும் என்ற விவரம் : 26-03-2008 பிற்பகல் 5-00 மணி வரை மேல்பட்டாம்பாக்கம், பேரூராட்சி அலுவலகம்.
 - செலுத்தப்பட வேண்டிய முன் வைப்புத் தொகை விபரம் : ரூ. 4700-00
 - நிறைவு செய்யப்பட்ட ஒப்பந்தப்புள்ளிகள் பெறப்படுவதற்கான கடைசி நாள், நேரம் மற்றும் இடம் : பேரூராட்சி அலுவலகம், மேல்பட்டாம்பாக்கம், 27-03-2008 பிற்பகல் 3.00 மணி வரை.
 - பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் திறக்கப்படும் இடம்,நாள்,நேரம் : பேரூராட்சி அலுவலகம், மேல்பட்டாம்பாக்கம், 27-03-2008 அன்று மாலை 3.30 மணி
 - ஒப்பந்தப்புள்ளி கோரும் அலுவலர் பொருத்தமானது என தீர்மானிக்கும் முக்கியமான தகவல். : ஒப்பந்ததாரர், மேல்பட்டாம்பாக்கம் பேரூராட்சியில் பதிவு செய்த, பண வரம்பு உடையவராக இருத்தல் வேண்டும். மேலும் ஒப்பந்ததாரர் தமது சொந்த பொறுப்பில் கட்டுமான பொருட்களைத் தரசான்றுடன் வெளிமார்ட்டுகெட்டிலிருந்து பெற்று உபயோகிக்க வேண்டும்.

(ஒப்பம்) திரு.வ.ஜெயமூர்த்தி
தலைவர்,
பேரூராட்சி மன்றம்,
மேல்பட்டாம்பாக்கம்.

(ஒப்பம்) திரு. மூ.கலைப்பாண்டி
செயல் அலுவலர்,
பேரூராட்சி அலுவலகம்,
மேல்பட்டாம்பாக்கம் .

SEHEDULE – A

NAME OF WORK : PROVIDING COMPOUND WALL AT COMPOST YARD IN MELPATAMPAKKAM TOWN PANCHAYAT

ISSUED TO :
EMD : 4700/- Executive Officer
DATE OF TENDER : 27.03.2008 Town Panchayat
CHALLAN NO : Melpattampakkam

- A) The quantities hereby given are these upon which the lump sum tender cost of the work is based but they are subject to alterations ,omissions, deductions or additions as provided for in the conditions of this contract and do not necessary show the actual quantities of work to be done. The Unit rates noted below or these covering payments for the extra or deduct as set forth in the preliminary specifications of Tamil Nadu standard specifications and New building cost and other conditions enclosed in the tender specification of this contract.
- B) It is to be expressly understood that measured work is to be taken net (Not with standing any custom or practice to the contrary) according to the actual quantities when place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer / Assistant Executive Engineer and the cost calculated to measurement or weight of the respective prices without any additional charges for any necessary of contingent works connected herewith. The rates are for works in site and complete every respect.

VALUE OF CONTRACT : 4,61,557/-
ESTIMATE COST : 4,70,000 /-

Item No. 1.	Probable Quantity 2.	Description of Work 3.	Unit in Words 4.	Rate In	
				Figures 5.	Words 6.
1.	160.00m3	Earth work excavation in all classes of soils with initial lead and lift etc., complete as per standard specification. Earth work excavation in all classes of soils such as hard stiff clay, stiff black cotton, hard red earth, shales, murrum, ordinary earth, earth mixed with 50% fairsized boulders etc., with initial leads and lift including laying, spreading, leveling, sectioning, breaking clods etc., as per SS 20 B and all other incidental charges etc., complete as per standard specification	One cubic metre		

Assistant Engineer
Town Panchayat Works
Vadalur.

Signature of Contractor :

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

No. of Corrections :

No. of over writings :

2.	24.00 m3	Sand filling with good river sand in basement. The charges Inclusive of cost and conveyance of all materials and all labour charges.etc complete.	One cubic metre		
3	24.00 m3	P.C.C 1:5:10 mix using 40mm ISS HBG metal. The charges Inclusive of all cost and conveyance of material, labour. Transportation charges, lead etc, complete.	One cubic metre		
4	55.00 m3	Brick work in cm 1:5 using 1 st class country bricks, with proper pointing, all material, including all labour charges. etc complete .as per standard specification.	One cubic metre		
5.	630.00 m2	Plastering with cm 1:5 mix 10 mm thick The charges inclusive cost and conveyance and all labours etc complete..as per standard specification.	One Square metre		
6.	210.00 m2	Towards centering charges for RCC items side and soffit of concrete works . The charges inclusive of form work, all material, Nails. Labour, etc..as per standard specification.	One Square metre		

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

Signature of Contractor :

No. of Corrections :

No. of over writings :

7.	41.00 m ³	Cement Concrete 1:2:4 mix (one cement two and four aggregate) using 20 mm I.R.C.H.B.G. metal including cost of forming the form work and laying the concrete inside the form work to proper gradient with required expansion joint etc wherever necessary including consolidation by wooden rammer including of cost curing up to the specified period as per standard specification.	One cubic metre		
8.	3000.00 Kg	Towards cost and supply of steel reinforcement as per drawing. The charges inclusive of cutting, bending, BarBending wire, Nails, labour, all material etc.complete. as per standard specification.	One Kilo gram		
9.	300.00 Kg	Supply and fixing of grill items of work. The charges inclusive of material, cutting, welding, labour, etc. complete. as per standard specification.	One Kilo gram		
10.	300.00 Kg	Supply and fixing of grill items of work.(Ornamental work). The charges inclusive of material, cutting, welding, labour, etc. complete. as per standard specification.	One Kilo gram		
11.	630.00 m ²	Colour washing using best colour pigments. The charges inclusive of material, Colour pigments, labour, etc. complete. as per standard specification.	One Square metre		
12.	30.00 m ²	Labour charges for painting work(New grill surface). The charges inclusive of material, Paints, labour, etc. complete. as per standard specification.	One Square metre		

Assistant Engineer
Town Panchayat Works
Vadalur.

Assistant Executive Engineer
Town Panchayat Works
Cuddalore Zone.

Signature of Contractor :

No. of Corrections :

No. of over writings :