

SCHEDULE - A

**NAME OF WORK : CONSTRUCTION OF RCC SLAB CULVERT @ KASAPPAI STREET
IN SRIMUSHNAM TOWN PANCHAYAT**

NAME OF TOWN PANCHAYAT : SRIMUSHNAM

DATE OF TENDER :

ESTIMATE COST : 75,000/-

SOLD TO :

Item No. 1	Probable Quantity 2.	Description of Work 3.	SSRB/M OST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1	30.00 Cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stoney each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus each as shown by the departmental officers at site as per standard specifications.				
2	4.00cum	Sanfilling with dry with river sand including all Labour charges etc completed				
3	26.00 sqm	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including cost and conveyance of all materials to site and all other incidental charges etc., complete.				

4	4.00 cum	Cement concrete 1:4:8 (One cement four sand and Eight hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.				
5	11.00 cum	Brick work in cement mortar 1:5 mixing using country bricks including Cost & Conveyance to site of all labour charges and all other mudental charges etc completed.				
6	54.00 sqm	Plastering with C.M.1:4 Mix to 12mm thick including cost and Conveyance of all materials to site and including all labour charges for mixing, laying watering and curring etc complete.				
7	2.00cum	PCC 1:2:4 mix using 20mm ISS HBG Metal including all labour charges etc. completed.				
8	7qtl	Supply and Fabrication of Steel				
9	5.50cum	RCC 124 1:2:4 mix using 20mm ISS HBG Metal including all labour charges etc. completed.				

Signature of Contractor

Junior Engineer
Town Panchayat
Annamalainagar

No. of corrections :
No.of overwritings:

Assistant Executive Engineer
Town Panchayat Works
Cuddalore.

SCHEDULE - A

NAME OF WORK: CONSTRUCTION OF SIDE DRAIN AT KOMBADI STREET IN SRIMUSHNAM TOWN PANCHAYAT.

NAME OF TOWN PANCHAYAT : SRIMUSHNAM

DATE OF TENDER :

ESTIMATE COST : 2,00,000/-

SOLD TO :

Item No. 1	Probable Quantity 2.	Description of Work 3.	SSRB/M OST 4.	Unit in Words 5.	Rate In	
					Figures 6.	Words 7.
1.	81.00 Cum	Earthwork excavation for foundation with initial lead of 10 meters and lift of 2 meters in Hard stiff clay stiff block cotton, Hard red earth skales Muram, Gravel Stoney each and earth mixed with small size of bolders and hard gravelly soil to full depth of foundation including shoring shuttering and baling out water wherever necessary and refilling the sides of foundation with excavation earth in layers of 15cm rammed well and consolidated and depositing the surplus earch as shown by the departmental officers at site as per standard specifications.				
2.	204.00 Sqm.	Towards centering charges for concrete sides including cost of centering and all labour charges for fixing proper alignment including conveyance of all materials to work site and other incidental charges etc., complete.				
3.	25.00 Cum	Cement concrete 1:3:6 (One cement three sand and Six hard broken stone) using 20mm ISS gauage hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of Materials at site and labour charges complete complying with standard specifications.				

4.	10.00 Cum	Cement concrete 1:4:8 (One cement four sand and Eight hard broken stone) using 40mm ISS gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers not more than 15 cm in thick etc., including cost of materials at site and labour charge complete complying with standard specification.				
5.	10.00 Cum	Sand filling with good river sand including all labour charges etc. completed.				

Signature of Contractor

No. of corrections :
No.of overwritings:

Junior Engineer
Town Panchayat
Annamalainagar

Assistant Executive Engineer
Town Panchayat Works
Cuddalore.